

(B)	BAS ENERGY SEE	VICES	1700 S. Country Estates Raod Liberal, KS 67901 PH (620)-624-2277FAX (620) 624-2280	SERVICE ORDER -	1718 19776 L
			111(020)-024-22111 AX (020) 024-2200	Date:	10/8/2019
Well Name:	FF 64512			Location:	
VIoIz # 1-12 A County - State:				26-23S-35W RRC #:	
Kearny, Kansa				KKC#.	
Type Of Service	e:	1.15		Customer's Order #:	
Z-42 Cement	Surface Casin				
	Customer: N	/lerit Ener	gy		
	Address: 0	ardencity	.invoices@meritenergy.com		
	111111111111111111111111111111111111111		50 Holcomb Ks 67861		
the collection costs ar	nd attorney fees. These	terms and cond	by Basic Energy Services In accord with the rates and terms stated in Basic Energy Services current price lists, Invoices are payable omer agrees to pay interest thereon after default at 198% per annum. In the event it becomes necessary to employ an attorney to enfitions shall be governed by the laws of the state where services are performed or equipment or materials are furnished. upplies and materials and that the same are free from defects in workmanship. THERE ARE NO WARRANTIES, EXPRESS OR IMF ID BEYOND THOSE STATED IN THE IMMEDIATELY PRECEDING SENTENCE. Basic Energy Services, liability and Customer's en	orce collection of said account, Custor	ner agrees to pay all
contract, tort, product	hability, breach of warra	anty or otherwis	e) arising out of the sale or use of any products, supplies, or materials upon their return to Basic Energy Services, is expressly limite Customer of credit for the cost of such items. In no event shall Basic Energy Services be liable for special, indirect, punitive or consu	d to the replacement of such products	supplies or materials
CODE	QTY	UOM	DESCRIPTION	PRICE	TOTAL
3C118	515	EA	A-Con Blend	50.00	25750.00
3C101	165	SK	Class C Cement	29.00	4785.00
CC102 CC109	299 1767	LB LB	Celloflake Calcium Chloride	4.00 1.00	1196.00 1767.00
CC201	516	LB	Gilsonite	1.00	516.00
WE102	180	MI	Heavy Equipment Mileage	8.00	1440.00
CE240	680	SK	Blending & Mixing Service Charge	1.40	952.00
ГМ	1923	MI	Ton Mileage	3.00	5769.00
CC2	1	HR	Depth Charge, 1001'-2000'	1500.00	1500.00
CE504	1	EA	Plug Container Utilization Charge	250.00	250.00
VIE101	60	MI	Light Vehicle Mileage	5.00	300.00
CE505	1	EA	Cement Densiometer, with chart recorder	350.00	350.00
CF105	1	Ea	Top Rubber Cement Plug, 8 5/8"	225.00	225.00
BE143	1	EA	Supervisor	75.00	75.00
BE144	1	EA	Driver	35.00	35.00
		· · · · · · · · · ·			
		-			
		19			
				MILLER TO A MILLER	
		<u> </u>			
				5 1 7 1	0// 0:0
				Book Total:	\$44,910.00
				Taxes:	045.004.:=
			Additional 10% Discount as per Agreement on Cement Services	Disc. Price:	\$15,024.47
	V	~	Additional 10% Discount as per Agreement on Cement Services	10% Disc Adjusted Price	\$1,502.45 \$13,522.02
				YES	
UMP TRUCK NU	JMBER: 37	223 19572	THIS JOB WAS SATISFACTORILY COMPLETED		NO
,	1 1	: ^	OPERATION OF EQUIPMENT WAS SATISFACTORY	Ī	i
RIVER:	1160	Hain	PERFORMANCE OF PERSONEL WAS SATISFACTORY	Ē	
11	19	0	P		
010	fer 6	16	27/170		
В	ASIC ENERGY S	ERVICES	CUSTOMER OR H	IS AGENT	
Custom	er Comments or	Concerns:			
1 m	ea Bi	ack	sher		
Last	1				
	-				




Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING JO

Job Log

						THE RESERVE THE PERSON NAMED IN COLUMN 2 I		The state of the s				
Customer:		Merit Energy			Cement Pump No.:	37223 1957	2 14HRS	Operator TRK No.:	8653			
Address:	gardencity.invoices@meritenergy.cor			Ticket #:	1718 19	776 L	Bulk TRK No.:1	Bulk TRK No.: 27808 19578 30464 3754 Kirby Corey				
City, State, Zip:	PO Box 250 Holcomb Ks 67861				Job Type:		Z-42 Cem	cement Surface Casing				
Service District:		18-Liberal KS			Well Type:			OIL				
l Name and No.:	Molz 4	# 1-12 AFE 64	1513		Well Location:	26-23S-35W	County:	Kearny	State:	Kansa		
Type o	f Cmt	Sacks			Additives			Truck Loa	ded On			
		515	3% Ca	alcium (Chloride, 1/2# Cellofl	ake, 1# Gilsonite	27808 19	578 Kirby	Front	Back		
A-Con Cement		313	0,000				2010107	-47.0	Front	Pool		
Class C (Cement	165		2% Ca	Ilcium Chloride, 1/4#	Celloflake	30464 375	547 Corey	Front	Back		
									Front Hours / Person	Back		
Lead	Tail:	Weight #1 Gal.		-t/sk	Water Requ	NAME OF TAXABLE PARTY.	CU. FT.		48	nei		
Lea	nd:	12.1	2.41		13.9		1241.15	TT Man Hours:				
Ta	il:	14.8	1.34		6.33		221.1	# of Men on Job: 3				
Time		Volume	Pu	imps	Pressu	ıre(PSI)	D	escription of Oper	ation and Materials	5		
(am/pm)	(BPM)	(BBLS)	Т	С	Tubing	Casing						
15:00pm						and the second second		Arrived at				
15:30pm								Spot trucks/Rig up Safety meeting				
17:30pm												
17:58pm						1500		Pressure test lines to 1500psi				
18:01pm	3	10				300	Pump 10bbls of fresh water spacer					
18:03pm	6	221				350	Pump 221bbls of lead from 515sks at 12.1lbs					
18:51pm	6	39				100	Pump 39bbls of tail from 165sks at 14.8lbs					
19:07pm								own/Drop plug/Wash pump and lines				
19:09pm							Start disp	lacement of 1	cement of 112bbls with fresh wate			
19:15pm	5	20				100		20bbls gone				
19:19pm	5	40				220		40bbls gone				
19:24pm	5	60				320		60bbls gone				
19:28pm	5	80				500		80bbls gone				
19:32pm	5	100				700	1	100bbls gone/Slow down rate				
19:36pm	3	112				1200	В	Bump plug/Hold for 2 minutes				
19:38pm					*		Relea	se pressure to	check if float	nolds		
			+				Got 40 bbls of cement to Surface					
		1		+			GC	of 40 ppis of ce	silicit to ourid			
							Rig down					
								Job cor	mpleted			
					7		TL	akad samaan	man and rig o	rew		
01 111	46.44	D	-		1017	Thanked compar		Float Collar				
Size Hole	12 1/4	Depth	1	207	1817 New / Used		Float Collar	1765.35	Depth			
Size & Wt. Csg.	8 5/8 24#			807	INEW / USed		Retainer	1	Depth			
Landing Psi Shoe Joint	500+	Depth	+		1		Perfs		CIBP			
SHOE JOHN	41.65	Туре			1	Basic Repres		\	/ictor A. Coron	a		
Customer Signature:					Basic Repres		The for a Corn					
Customer Signature.						Date of Service	-100-100-100-100-100-100-100-100-100-10	0	10/8/2019			



Pumping Order / Mixture

Client:

Merit Energy

Date:

10/8/2019

Job:

8 5/8 Surface

Well Name & No: Molz 1-26

Location Supervisor: Victor A. Corona

COMPANY REP. Rodney Gonzales

Differential Pressure

1477 psi

Lift Pressure:

500 psi

Recipe

Pressure Test PSI: 1500

MAX PSI: 500

10 BBLS OF FRESH WATER SPACER

221 BBLS LEAD SLURRY YIELD 2.41 12.1LBS 515SKS 13.9G/SK

39 BBLS TAIL SLURRY YIELD 1.34

14.8LBS

165SKS 6.33G/SK

DROP PLUG/WASH PUMP ON TOP OF PLUG

112.0 BBLS OF DISPLACEMENT

100.0 BBLS @ 5 BPM

12.0 BBLS AT 2-3 BPM TO BUMP PLUG

DISP PLUG WITH 112 BBLS OF H20



				Service	ce Point Liberal, Kansas					
Company		Merit Energy		Contact		-	e Davis	PI	h#	620-388-3779
ell Type		Contractor	Duke		Cou		Kearn		ate	Kansas
ease		Molz		26 Se		26		00	nge	35W
irections:										
Garden C	City Ks: Wo	est on Hwy 50 to Finn			; 1 mile o locatio		to CR AA; 2	miles nort	th to	CR 210; 0.6 m
Job Type					Casing Size		Thread	vveight		10 III
		Surface		_	Tubing/Drill Pip	5/8 e Size	8 R	ind Weight		24
Equipiment		1 Pump Truck 2 Bulk		Hole Size Packer Bridge Plug					N. W. W.	
AFE#:					Plug Container	2 1/4	Squeeze Mar	ifold Field Bi	'n	*
		Surface: 8 5/8 F	E On Locat	tion: Re		Yes	ng his on th	is well		
		Juilace. 0 5/0 F		EMENT		, uəl	ing ma on th	14011		
LEAD 1	Weight PPG	Туре			Additives 3% Calcium Chloride, 1/2# Celloflake, 1# Gilsonite					
BC118	12.1	A-Con	Cement Water Gal/sk							
515	130%	2.41	13.9	0						
TAIL 1 BC101	Weight PPG	Type Class C		Additives 2% Calcium Chloride , 1/4 # Celloflake						
165	Excess	Yield FP/sk 1.34	Water Gal/sk	3						
LEAD 2	Weight PPG	Турс			Additives					
ncks	Excess	Yield Fe'sk	Water Gal/sk							
TAIL 2	Weight PPG		1		Additives			***		
neks	Excess	Yield Ft ^e /sk	Water Gul/sk							
Mouse/Rat	Weight PPG	Туре			Additives					
acks	Excess	Yield Ft ^o /sk	Water Gal/sk							
Plugs	Weight PPG	Туре			Additives	2				
acks	Excess	Yield Fe/sk	Water Gal/sk							
			Flo	oat Equi	ipment					
Part#	Quanity	Descr						# Used		# Returned
CF105	11_	Top Rubber Cement	Plug, 8 5/8"						-	
									+	
								ar manual a		
									+	
11.00-1									+-	
			M	isc. Che	micals					
rdered By	Luke Lau	Phone	972-628-10	680 =	ax		Date of J	ob		3
all Taken By	Max Ball	Phone			mail		Time Res	ndy		
	Driver									