



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING

Job Log

Customer:	Merit Energy	Cement Pump No.:	38750-19842	Operator TRK No.:	96815
Address:	gardencity.invoices@meritenergy.com	Ticket #:	1718-19750	Bulk TRK No.:	14354-19808
City, State, Zip:	PO Box 250 Holcomb Ks 67851	Job Type:	Z-42 Cement Production Casing		
Service District:		Well Type:	OIL		
Well Name and No.:	Molz #1-26 AFE # 64513	Well Location:	26-23S-35W	County:	Kearny
				State:	Kansas

Type of Cmt	Sacks	Additives	Truck Loaded On		
CLASS C 50/50 POZ	250	6%GYPSUM, 10%SALT, .5%C-17, 1/4#DEFOAMER, 5#GILSONITE, 1/4#POLYFLAKE	14354-19808	Front	Back
				Front	Back
				Front	Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
Lead:	13.6	1.57	7.18	392.5	Man Hours:	22
Tail:					# of Men on Job:	3

Time (am/pm)	(BPM)	Volume (BBLS)	Pumps		Pressure(PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
8:30							ON LOC, SAFTET MTG, R.U.
10:35						3500	TEST LINES
10:37 AM	1.7	12				170	PUMP MUD FLUSH
10:42 AM	3.1	5				260	H2O SPACER
10:47 AM							PLUG RAT AND MOUSE
10:56	7					430	START MIXING 200SX @ 13.6#
11:10		56					SHUT DOWN, DROP PLUG, WASHUP
11:19 AM	7					160	START DISPLACEMENT
11:41	2.4	105				780	SLOW RATE
11:45		115				980-1580	PLUG DOWN
11:50							RELEASE PSI, FLOAT HELD
							JOB COMPLETE
							THANK YOU FOR YOUR BUSINESS!!!

Size Hole	7 7/8	Depth	5015'		TYPE	
Size & Wt. Csg.	5 1/2 17	Depth	5015'	New / Used	Packer	Depth
tbg.		Depth			Retainer	Depth
Shoe	42.93'	Type			Perfs	CIBP

Customer Signature:	Basic Representative:	CHAD HINZ
	Basic Signature:	
	Date of Service:	10/12/2019

