

Form	ACO1 - Well Completion
Operator	McGowan Oil Company, a General Partnership
Well Name	OLSEN 17-1
Doc ID	1616811

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	12.25	8.625	23	318	class A	185	Class A Kol Seal
Production	7.875	5.50	15.5	2855	Thick set	170	Thickset Kolseal and Phenoseal

Elite Cementing & Acidizing of KS, LLC
PO Box 92
Eureka, KS 67045



Date	Invoice #
10/19/2021	5933

Bill To	
McGowan Oil Company 302 Summit Arkansas City, KS 67005	
Customer ID#	1273

Job Date	10/12/2021
Lease Information	
Olsen #17-1	
County	Cowley
Foreman	KM

Item	Description	Qty	Terms	Net 15
			Rate	Amount
C102	Cement Pump-Longstring	1	1,100.00	1,100.00
C107	Pump Truck Mileage (one way)	80	4.20	336.00
C201	Thick Set Cement	170	22.55	3,833.50T
C207	KolSeal	850	0.52	442.00T
C208	Pheno Seal	340	1.45	493.00T
C108B	Ton Mileage-per mile (one way)	748	1.40	1,047.20
C421	5 1/2" Latch Down Plug	1	266.00	266.00T
C661	5 1/2" AFU Float Shoe	1	340.00	340.00T
C604	5 1/2" Cement Basket	1	260.00	260.00T
C504	5 1/2" Centralizer	8	55.00	440.00T
C222	KCL	1	30.00	30.00T
D101	Discount on Services		-124.15	-124.15
D102	Discount on Materials		-305.23	-305.23T

We appreciate your business!

Phone #	Fax #	E-mail
620-583-5561	620-583-5524	rene@elitecementing.com

Send payment to:
Elite Cementing & Acidizing of KS, LLC
PO Box 92
Eureka, KS 67045

Subtotal	\$8,158.32
Sales Tax (6.5%)	\$376.95
Total	\$8,535.27
Payments/Credits	\$0.00
Balance Due	\$8,535.27

pd 11/12/21
2617



ELITE
CEMENTING & ACID SERVICE, LLC

C & G
DR19
R19 #2

Ticket No. **5933**

Foreman Kevin McCoy

Camp Eureka

Job Type <u>Longstring</u>	Hole Depth <u>3024' K.B.</u>	Slurry Vol. <u>44 BBL SLURRY</u>	Tubing _____
Casing Depth <u>2855 G.L.</u>	Hole Size <u>7 7/8"</u>	Slurry Wt. <u>13.8 #</u>	Drill Pipe _____
Casing Size & Wt. <u>5 1/2</u>	Cement Left in Casing <u>0'</u>	Water Gal/SK _____	Other _____
Displacement <u>68.5 BBL</u>	Displacement PSI <u>750</u>	Bump Plug to <u>1250 PSI</u>	BPM _____

Remarks: SAFETY Meeting: 5 1/2" CASING Set @ 2855' G.L. Rig up to 5 1/2" CASING. BREAK Circulation w/ 10 BBL Fresh water. Mixed 135 SKS THICK Set Cement w/ 5* Kcl-SEAL/SK, 2* PhenoSEAL/SK @ 13.8th /GAL yield 1.85 = 44 BBL Slurry. Wash out Pump & Lines. Shut down, Release Latch down Plug. Displace Plug to Seat w/ 68.5 BBL Fresh water. (Kcl in first 20 BBL). FINAL Pumping Pressure 750 PSI. Bump Plug to 1250 PSI. Wait 2 mins. Release Pressure. Float & Plug Held. Good Circulation @ ALL times while Cementing. Job Complete. Rig down.

Plug R.H. & M.H.

Centralizers on #1, 3, 9, 10, 11, 15, 16, 17 Basket on Top of #1

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 102	1	Pump Charge	1100.00	1100.00
C 107	80	Mileage	4.20	336.00
C 201	170 SKS	THICK Set Cement	22.55	3833.50
C 207	850 *	KOL-SEAL 5*/SK	.52 *	442.00
C 208	340 *	PhenoSEAL 2*/SK	1.45 *	493.00
C 108 B	9.35 TONS	TON Mileage 80 miles	1.40	1042.20
C 421	1	5 1/2 LATCH down Plug	266.00	266.00
C 661	1	5 1/2 AFU FLOAT Shoe w/ LATCH down	340.00	340.00
C 604	1	5 1/2 Cement Basket	260.00	260.00
C 504	8	5 1/2 x 7 7/8 Centralizers	55.00	440.00
C 222	1 gals	KCL (in First 20 BBL Displacement water)	30.00	30.00
			Sub TOTAL	8581.70
			Less 5%	(449.82)
			Sales Tax	396.19

Authorization Witnessed By Judd Gulick Title C#6 Dr/g Toolpusher

Total

8535.21

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.

Elite Cementing & Acidizing of KS, LLC
PO Box 92
Eureka, KS 67045



Date	Invoice #
10/12/2021	5986

Bill To	
McGowan Oil Company 302 Summit Arkansas City, KS 67005	
Customer ID#	1273

Job Date	10/8/2021
Lease Information	
Olsen 17-1	
County	Cowley
Foreman	RM

Item	Description	Qty	Terms	Net 15
			Rate	Amount
C101	Cement Pump-Surface	1	890.00	890.00
C107	Pump Truck Mileage (one way)	80	4.20	336.00
C200	Class A Cement-94# sack	185	17.35	3,209.75T
C205	Calcium Chloride	520	0.69	358.80T
C206	Gel Bentonite	350	0.28	98.00T
C209	Flo-Seal	45	2.60	117.00T
C108B	Ton Mileage-per mile (one way)	688	1.40	963.20
D101	Discount on Services		-109.46	-109.46
D102	Discount on Materials		-189.17	-189.17T

We appreciate your business!

Phone #	Fax #	E-mail
620-583-5561	620-583-5524	rene@elitecementing.com

Send payment to:
Elite Cementing & Acidizing of KS, LLC
PO Box 92
Eureka, KS 67045

Subtotal	\$5,674.12
Sales Tax (6.5%)	\$233.63
Total	\$5,907.75
Payments/Credits	\$0.00
Balance Due	\$5,907.75

*pd
11/12/21
2617*



Ticket No. **5986**

Camp EUREKA

Remarks: Safet meeting + Job procedure, log to 8-1/8 casing
Break circulation w/ 10 bbl water mix 185 grs class A. King
39 cncs 2% cel 1/4" Fluoride @ 15# = 41 Slurry Visc 1.36
Displace w/ 10 1/2 water @ bbl Slurry to pit. close casing in.
Job complete - Teni, Louis. Thank you.

[illegible]

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.

Conservation Division
266 N. Main St., Ste. 220
Wichita, KS 67202-1513



Phone: 316-337-6200
Fax: 316-337-6211
<http://kcc.ks.gov/>

Dwight D. Keen, Chair
Susan K. Duffy, Commissioner
Andrew J. French, Commissioner

Laura Kelly, Governor

February 07, 2022

Dan McGowan
McGowan Oil Company, a General
Partnership
302 N SUMMIT ST
ARKANSAS CITY, KS 67005-2296

Re: ACO-1
API 15-035-24741-00-00
OLSEN 17-1
SW/4 Sec.17-35S-07E
Cowley County, Kansas

Dear Dan McGowan:

K.A.R. 82-3-107 provides for all completion information to be filed within 120 days of the spud date. Subsection(e)(2) of that regulation states "All rights to confidentiality shall be lost if the filings are not timely."

The above referenced well was spudded on 10/08/2021 and the ACO-1 was received on February 06, 2022 (not within the 120 days timely requirement).

Therefore, your request for confidential treatment of data contained within the ACO-1 filing cannot be granted at this time.

If you should have any questions, please do not hesitate to contact me at (316)337-6200.

Sincerely,

Production Department