

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form U3C
June 2015
Form must be Typed
Form must be completed
on a per well basis

**ANNUAL REPORT OF PRESSURE MONITORING,
FLUID INJECTION AND ENHANCED RECOVERY**

Complete all blanks - add pages if needed. Copy to be retained for five (5) years after filing date.

OPERATOR: License # _____
Name: _____
Address 1: _____
Address 2: _____
City: _____ State: _____ Zip: _____ + _____
Contact Person: _____
Phone: (_____) _____
Lease Name: _____
Well Number: _____

API No.: _____
Permit No.: _____
Reporting Year: _____
(January 1 to December 31)
____ - ____ - ____ - ____ Sec. ____ Twp. ____ S. R. ____ E W
(a/a/a/a)
_____ feet from N / S Line of Section
_____ feet from E / W Line of Section
County: _____

I. Injection Fluid:

Type (Pick one): Fresh Water Treated Brine Untreated Brine Water/Brine
Source: Produced Water Other (Attach list)
Quality: Total Dissolved Solids: _____ mg/l Specific Gravity: _____ Additives: _____
(Attach water analysis, if available)

II. Well Data:

Maximum Authorized Injection Pressure: _____ psi Injection Zone: _____
Maximum Authorized Injection Rate: _____ barrels per day
Total Number of Enhanced Recovery Injection Wells Covered by this Permit: _____ (Include TA's)

III.	Month:	Total Fluid Injected BBL	Maximum Fluid Pressure	Total Gas Injected MCF	Maximum Gas Pressure	# Days of Injection
	January	_____	_____	_____	_____	_____
	February	_____	_____	_____	_____	_____
	March	_____	_____	_____	_____	_____
	April	_____	_____	_____	_____	_____
	May	_____	_____	_____	_____	_____
	June	_____	_____	_____	_____	_____
	July	_____	_____	_____	_____	_____
	August	_____	_____	_____	_____	_____
	September	_____	_____	_____	_____	_____
	October	_____	_____	_____	_____	_____
	November	_____	_____	_____	_____	_____
	December	_____	_____	_____	_____	_____
	TOTAL	_____	_____	_____	_____	_____

Complete Water Analysis Report

Customer: SHAKESPEARE OIL COMPANY
 Region: Kansas
 Location: Lane County
 System: Production System

Equipment: Schoepf 2-15 SWD
 Sample Point: Bleeder
 Sample ID: AS88283
 Acct Rep Email: Michael.Walters@championx.com

Collection Date: 02/03/2022
 Receive Date: 02/07/2022
 Report Date: 02/08/2022
 Location Code: 430658

Field Analysis

Bicarbonate	224.00 mg/L	Dissolved CO2	246.00 mg/L	Dissolved H2S	37.00 mg/L
Pressure Surface	25 psi	Temperature	100 °F	pH of Water	7.50

Sample Analysis

Ionic Strength	0.83 mol/L	Specific Gravity	1.037	Total Dissolved Solids	46227.94 mg/L
----------------	------------	------------------	-------	------------------------	---------------

Cations

Iron	0.449 mg/L	Manganese	0.042 mg/L	Barium	0.141 mg/L
Strontium	34.91 mg/L	Calcium	919.3 mg/L	Magnesium	354.1 mg/L
Sodium	15030.00 mg/L				

Anions

Chloride	27997 mg/L	Sulfate	1668 mg/L
----------	------------	---------	-----------

Scale Type

Anhydrite CaSO4 PTB	N/A	Anhydrite CaSO4 SI	-0.85
Barite BaSO4 PTB	N/A	Barite BaSO4 SI	-0.01
Calcite CaCO3 PTB	17.1	Calcite CaCO3 SI	0.13
Celestite SrSO4 PTB	N/A	Celestite SrSO4 SI	-0.21
Gypsum CaSO4 PTB	N/A	Gypsum CaSO4 SI	-0.71
Hemihydrate CaSO4 PTB	N/A	Hemihydrate CaSO4 SI	-0.68

Comments

Scaling predictions calculated using Odco-Tomson model

This document contains the confidential and/or proprietary information of ChampionX. The recipient agrees to maintain the confidentiality of the terms of this document, and shall not reproduce it by any means, disclose the contents of it to any third party, or use the contents of it for any purpose other than the purpose for which it was intended by ChampionX.