

ALT ☐ I ☐ II ☐ III Approved by: _____ Date: _____

Form	ACO1 - Well Completion
Operator	RJ Energy, LLC
Well Name	EASTBURN 24I
Doc ID	1674509

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	9.875	7	17	20	portland	8	n/a
Production	5.875	2.875	9	665	portland	80	n/a

Eastburn 24I

1	soil	1	start 8/17/2022
9	clay and rock	10	finish 8/18/2022
49	shale	59	
148	lime	207	
174	shale	381	
16	lime	397	set 20' 7"
55	shale	452	ran 665' 2 7/8
33	lime	485	cemented to surface 80 sxs
28	shale	513	
16	lime	529	
9	shale	538	
8	lime	546	
8	shale	554	
5	lime	559	
24	shale	583	
3	sandy shale	586	odor
13	bkn sand	599	show
6	oil sand	605	show
22	oil sand	627	good show
48	shale	675	td

HAMMERSON CORPORATION

PO BOX 189
Gas. KS 66742

Invoice

Date	Invoice #
8/25/2022	21442

Bill To

R.J. ENERGY LLC
22082 NE NEOSHO RD
GARNETT, KS 66032

P.O. No.

Terms

Project

Due on receipt

Quantity	Description	Rate	Amount
160	Well Mud (\$8.80 Per Sack) Ewing Lease Ticket #21442	8.80	1,408.00T
2.5	Hour Rate	65.00	162.50T
1	Fuel Surcharge	35.00	35.00T
160	Well Mud (\$8.80 Per Sack) Eastburn 101 & 71 Ticket #21449	8.80	1,408.00T
1	Hour Rate	65.00	65.00T
1	Fuel Surcharge	35.00	35.00T
100	Well Mud (\$8.80 Per Sack) Eastburn 251 Ticket #21463	8.80	880.00T
1	Hour Rate	65.00	65.00T
1	Fuel Surcharge	35.00	35.00T
100	Well Mud (\$8.80 Per Sack) Eastburn 201 Ticket #21480	8.80	880.00T
1	Hour Rate	65.00	65.00T
1	Fuel Surcharge	35.00	35.00T
160	Well Mud (\$8.80 Per Sack) Eastburn 241 Ticket #21483	8.80	1,408.00T
1.2	Hour Rate	65.00	78.00T
1	Fuel Surcharge	35.00	35.00T
	SALES TAX	6.50%	428.64
<i>Created to guitar with company tools</i>			
Thank you for your business.		Total	\$7,023.14