

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4

March 2009

Type or Print on this Form

Form must be Signed

All blanks must be Filled

OPERATOR: License #: 5039
Name: AGV Corp.
Address 1: 123 N MAIN
Address 2: PO BOX 377
City: ATTICA State: KS Zip: 67009 + 0377
Contact Person: Kent Roberts
Phone: (620) 254-7222
Type of Well: (Check one) ☐ Oil Well ☒ Gas Well ☐ OG ☐ D&A ☐ Cathodic
☐ Water Supply Well ☐ Other: ☐ SWD Permit #: ☐ ENHR Permit #: ☐ Gas Storage Permit #: ☐
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 4382 Bottom: 4390 T.D. 4330
Herington Depth to Top: 1652 Bottom: 1656 T.D. 1783
Depth to Top: Bottom: T.D.

API No. 15 - 15-007-22622-00-01
Spot Description: SW-NE-SE-SE Sec. 22 Twp. 32 S. R. 10 ☐ East ☒ West
981 Feet from ☐ North / ☒ South Line of Section
352 Feet from ☒ East / ☐ West Line of Section
Footages Calculated from Nearest Outside Section Corner:
☐ NE ☐ NW ☒ SE ☐ SW
County: Barber
Lease Name: MARTIN Well #: 2
Date Well Completed: 11/14/2022 (Date)
The plugging proposal was approved on: 11/14/2022 (Date)
by: Ken Sullivan (KCC District Agent's Name)
Plugging Commenced: 11/21/2022
Plugging Completed: 11/21/2022

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8.625	236	0
		Production	5.5	4497	1237

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 1600', 2 sacks cement on top with dump bailer. Shot casing off @ 1237'. Pulled and lay down casing. Ran 2-7/8 tubing in hole
1st plug @ 630', displaced 5 sacks gel & 50 sacks cement.
2nd plug @ 270', displaced 50 sacks cement
3rd plug, @ 60', displaced and circulated cement to pit with 35 sx cement.
All cement 60/40 poz (4%gel) by Quality Well. Job complete 5 PM.

Plugging Contractor License #: 35456 Name: 4G Well Service LLC
Address 1: PO BOX 75187 Address 2:
City: WICHITA State: KS Zip: 67275 + 0187
Phone: (316) 215-1683
Name of Party Responsible for Plugging Fees: Operator
State of Kansas County, Sedgwick, ss.
Kent Roberts ☒ Employee of Operator or ☐ Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Submitted Electronically