

Form	ACO1 - Well Completion
Operator	RJ Energy, LLC
Well Name	EASTBURN-NICKEL 26
Doc ID	1679901

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	9.875	7	17	20	portland	8	n/a
Production	5.875	2.875	6	663	portland	80	n/a

Eastburn ²⁶~~28~~

3	soil	3	start 10/4/1991
7	clay and rock	10	finish 10/5/1991
88	shale	98	
102	lime	200	
179	shale	379	
18	lime	397	set 20' 7"
52	shale	449	ran 663' of 2 7/8
32	lime	481	cemented to surface 80 sxs
30	shale	511	with company tools
17	lime	528	
8	shale	536	
7	lime	543	
9	shale	552	
6	lime	558	
30	shale	588	
12	sandy shale	600	odor
22	oil sand	622	good show
41	oil sand	663	td