

Form	ACO1 - Well Completion
Operator	Colt Energy Inc
Well Name	CONLEY 26
Doc ID	1586255

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	11.25	8.625	24	20	Portland	8	None
Production	6.75	4.5	11.6	727	Thick Set (OWC)	85	Phenoseal

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561



Cement or Acid Field Report
Ticket No. **5666**
Foreman David Gardner
Camp Eureka

API # 15-001-31664

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
6-14-21	1003	Conley #26	19	23 S.	20 E.	Allen	KS
Customer	Colt Energy Inc.		Safety Meeting	Unit #	Driver	Unit #	Driver
Mailing Address	P.O. Box 388		DG JH BW	105	Jason		
City	State	Zip Code		112	Broker		
Iola	KS	66749					

Job Type Longstring Hole Depth 742' Slurry Vol. 28 Bbl Tubing _____
Casing Depth 726.65' Hole Size 6 3/4" Slurry Wt. 13.8# Drill Pipe _____
Casing Size & Wt. 4 1/2" 11.60# Cement Left in Casing 4' 5.5' Water Gal/SK 9.0 Other _____
Displacement 11 1/4 Bbl Displacement PSI 350 Bump Plug to 750 PSI BPM _____

Remarks: Safety Meeting. Rig up to 4 1/2" casing. Break circulation w/ 5 Bbl fresh water. Mix 200# Gel Flush w/ Hulls, 5 Bbl water spacer. Mixed 85 sks Thick Set Cement w/ 2# Phenoseal/sk @ 13.8#/gal, yield 1.85 = 28 Bbl slurry. Wash out pump & lines. Shut down. Release 4 1/2" Top Rubber Plug. Displace plug to seat w/ 11 1/4 Bbl fresh water. Final pumping pressure of 350 PSI. Bump plug to 750 PSI. Wait 2 mins. Release pressure. Float & Plug held. Good cement returns to surface = 6 Bbl slurry to pit. Job complete. Rig down.

Note: Well had casing head welded on because it was flowing.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C102	1	Pump Charge	890.00	890.00
C107	5	Mileage	4.20	210.00
C201	85 sks	Thick Set Cement	22.55	1916.75
C208	170#	Phenoseal 2#/sk	1.45	246.50
C108A	4.46 Tons	Ton Mileage - Bulk Truck	m/c	365.00
C206	200#	Gel Flush	.28	56.00
C214	40#	Hulls	.55	22.00
C403	1	4 1/2" Top Rubber Plug	53.00	53.00
Thank You			Sub Total	3,759.25
			Discount	< 301.15 >
			Sales Tax	154.42
			7.75%	
Authorization <u>Witnessed by Wes</u> Title <u>Co/Rep</u>			Total	3611.92

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.

Company/Operator Colt Energy Inc. P.O. Box 388 Iola, KS 66749	Well No. 26	Lease Name Conley	Well Location 2406' fsl, 1467' fwl	1/4 nw	1/4 ne	1/4 SW	Sec. 19	Twp. 23	Rge, 20E	
	Well API # 15-001-31664	Type/Well Oil	County Allen	State KS	Total Depth 741	Date Started 6/11/2021	Date Completed 06/16/2021			
	Surface Record		Bit Record		Coring Record					
	Bit Size: 11 1/4	Type PDC	Size 11 1/4	From 0'	To 20'	Core # 1	Size 3"	From 631	To 661	% Rec. 99
Driller/Crew Andy King	Casing Size: 8 5/8	PDC	6 3/4	20'	741	2	3"	661	689	99
Charles King	Casing Length: 20'									
	Cement Used: 8 sx									
	Cement Type: Portland									

Formation Record									
From	To	Formation	From	To	Formation	From	To	Formation	
0	12	overburden							
12	47	lime							
47	134	shale							
134	234	lime							
234	235	shale							
235	241	lime							
241	440	shale							
440	452	lime							
452	516	shale							
516	530	lime							
530	538	shale							
538	542	lime							
542	571	shale							
571	609	lime							
609	631	shale							
631	661	1st core							
661	689	2nd core							
689	741	shale							