






Form	ACO1 - Well Completion
Operator	Zeta Energy, LLC
Well Name	SHOFNER D4
Doc ID	1768391

#### Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	9.875	7	17	22	50/50 Poz	5	NA
Production	5.625	2.875	6.5	629	60/40 Poz	95	See Ticket on file



11 Lewis Drive

Paola, KS 66071

**Oil & Gas Well Drilling  
Water Wells  
Geo-Loop Installation**

Phone: 913-557-9083

Fax: 913-557-9084

**WELL LOG**

Diamond Star Oil, Inc.

Shofner #D4

API#15-121-31,102

October 19- October 20, 2015

<u>Thickness of Strata</u>	<u>Formation</u>	<u>Total</u>
1	soil & clay	1
15	lime	16
18	shale	34
17	lime	51
97	shale	148
18	lime	166
31	shale	197
4	lime	201
20	shale	221
14	lime	235
33	shale	268
27	lime	295 oil show
7	shale	302
22	lime	324
3	shale	327
16	lime	343 base of the Kansas City
127	shale	470
2	lime	472
21	shale	493
13	broken sand	506 brown & green, ok bleeding
7	shale	513
2	lime	515
7	shale	522
4	lime	526
32	shale	558
6	lime	564
17	shale	581
5	lime	586
10	shale	596
9	lime	605
41	shale	646
4	broken sand	650 brown & green, oil odor
9	silty shale	659
20	shale	679 TD

Drilled a 9 7/8" hole to 22.1'

Drilled a 5 5/8" hole to 679'

Set 22.1' of 7" surface casing cemented with 5 sacks of cement

Set 629' of new 2 7/8" 8 round upset tubing, 3 centralizers, 1 float shoe, and 1 clamp.