





Form	ACO1 - Well Completion
Operator	Massey, Gary R.
Well Name	LADD B 4
Doc ID	1784782

#### Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	12.25	8.625	17	117	Portland A	100	50/50 POZ
Surface	7.875	4.5	12	2557	Class A	50	50/50 POZ 2% Bentonite
Liner	5.625	2.875	8	2330	Class A	50	50/50 POZ 2% Bentonite

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company. LANCE HILL  
Farm. Ladd

No. 4

SEC. 25 T. 25 R. 3E  
NW SW SE

Total Depth. 2557'  
Comm. 8-26-65 Comp. 9-1-65  
Shot or Treated.  
Contractor. Eureka Drlg.  
Issued. 10-30-65

County Greenwood  
KANSAS



CASING:

4-1/2" @ 2557 w/50 sx. cement  
8 5/8" 117'--Cemented w/100 sacks Regular Cement

Elevation. 1304' KB

Production. DRY

Figures Indicate Bottom of Formations.

lime & soil	10
lime	60
shale	87
lime	165
shale & shells	700
lime	820
lime & shale	1160
shale	1225
sand	1320
sand & sandy shale	1460
lime & shale	1595
shale	1767
lime	1945
lime & shale	2085
shale w/lime strks	2200
lime & shale	2260
sand	2275
shale & lime	2400
sand & shale w/show free oil	2402
Core # 1	2444
shale	2402-2406
sand & shale	2406-2411
shale	2411-2412
sandy shale	2412-2415
sand w/shale	2415-2423
shale	2423-2425
sand w. good show oil	
and good Florescence	2425-2428
sand & shale	2437-2443
shale	2516
sand & shale	2528
shale	2557 RTD
Total Depth	

TOPS: SMP  
Bartlesville 2411

STATE RECEIVED  
MAR - 3 1962  
CONSERVATION DIVISION  
Wichita, Kansas