

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
March 2009
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

OPERATOR: License #: _____
 Name: _____
 Address 1: _____
 Address 2: _____
 City: _____ State: _____ Zip: _____ + _____
 Contact Person: _____
 Phone: (_____) _____
 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - _____
 Spot Description: _____
 _____ - _____ - _____ - _____ Sec. _____ Twp. _____ S. R. _____ East West
 _____ Feet from North / South Line of Section
 _____ Feet from East / West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: _____
 Lease Name: _____ Well #: _____
 Date Well Completed: _____
 The plugging proposal was approved on: _____ (Date)
 by: _____ (KCC District Agent's Name)
 Plugging Commenced: _____
 Plugging Completed: _____

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugging Contractor License #: _____ Name: _____
 Address 1: _____ Address 2: _____
 City: _____ State: _____ Zip: _____ + _____
 Phone: (_____) _____
 Name of Party Responsible for Plugging Fees: _____
 State of _____ County, _____, ss.
 _____ Employee of Operator or Operator on above-described well,
 (Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Submitted Electronically

QUALITY OILWELL CEMENTING, INC.

Federal Tax I.D.# 20-2886107

Phone 785-483-1071
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 4266

Date	10/29/24	Sec.	3	Twp.	11	Range	17	County	Ellis	State	Kansas	On Location		Finish	12:30pm
Location								183+River Rd SE 1/4 N E into							

Lease	Simpson	Well No.	A2	Owner	To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.
Contractor					
Type Job	plug				
Hole Size		T.D.		Charge To	H+C
Csg.	4 1/2	Depth		Street	
Tbg. Size	2 3/8	Depth	3300'	City	State
Tool		Depth		The above was done to satisfaction and supervision of owner agent or contractor.	
Cement Left in Csg.		Shoe Joint		Cement Amount Ordered	250 ⁶⁰ / ₄₀ 4% gel
Meas Line		Displace		600# gel 500# Hulls	

EQUIPMENT

Pumptrk	16	No.	Cementer	Tim	Common	150
			Helper		Poz. Mix	100
Bulktrk	9	No.	Driver	Corey	Gel.	15
			Driver		Calcium	
Bulktrk	14	No.	Driver	David	Hulls	500# (10)
			Driver		Salt	

JOB SERVICES & REMARKS

Remarks:	
Rat Hole	Flowseal
Mouse Hole	Kol-Seal
Centralizers	Mud CLR 48
Baskets	CFL-117 or CD110 CAF 38
D/V or Port Collar	Sand
3300'-mixed 600# gel followed by 50 sks with 150# Hulls	Handling 275
1667'-mixed 110 sks with 300# Hulls	Mileage
365'-mixed 60 sks with 50# Hulls to circulate to surface pulled tubing and topped off with 25 sks	FLOAT EQUIPMENT
Hooked to backside and mixed 5 sks	Guide Shoe
Backside was full	Centralizer
Cement did circulate	Baskets
	AFU Inserts
	Float Shoe
	Latch Down
Used 250 sks total	
600# gel 500# Hulls	Pumptrk Charge plug
	Mileage 37

X Signature	Bob Hunt	Tax	
		Discount	
		Total Charge	

Thanks