

Form	ACO1 - Well Completion
Operator	RJ Energy, LLC
Well Name	WOLF MCADAM 4
Doc ID	1835234

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	9.875	7	17	40	portland	5	
Production	5.625	2.875	6.5	902	portland	120	

RJ Energy, LLC

Drill Log - Cement Log

Lease:	Wolf McAdams	Start:	1/23/2025	Surface:	7 "	40 '	5 Sacks
Well#	4	Finish:	1/24/2025				
API#	15-207-30032			Longstring:	2.875 "	902 '	120 Sacks

Span	Formation	Depth	Notes
4	Top Soil	4	Pumped 120 sacks and circulated to the top using company tools.
18	Clay & Gravel	22	
67	Shale	89	
40	Lime	129	
49	Shale	178	
110	Lime	288	
42	Shale	330	
146	Lime	476	
189	Shale	665	
10	Lime	675	
59	Shale	734	
32	Lime	766	
12	Shale	778	
9	Lime	787	
11	Shale	798	
8	Lime	806	
11	Shale	817	
3	Lime	820	
38	Shale	858	
10	Broken Sand	868	
44	Shale	912	TD