

Form	ACO1 - Well Completion
Operator	RJ Energy, LLC
Well Name	WOLFE MCADAM 3
Doc ID	1835233

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	9.875	7	17	40	portland	5	
Production	5.625	2.875	6.5	895	portland	120	

RJ Energy, LLC

Drill Log - Cement Log

Lease: Wolf McAdams	Start: 1/15/2025	Surface: 7 " 40 ' 5 Sacks
Well# 3	Finish: 1/16/2025	
API# 15-207-29986		Longstring: 2.875 " 895 ' 120 Sacks

Span	Formation	Depth	Notes
5	Top Soil	5	Pumped 120 sacks and circulated to the top using company tools.
20	Clay & Gravel	25	
35	Shale	60	
38	Lime	98	
82	Shale	180	
104	Lime	284	
46	Shale	330	
142	Lime	472	
190	Shale	662	
10	Lime	672	
60	Shale	732	
30	Lime	762	
16	Shale	778	
9	Lime	787	
13	Shale	800	
4	Lime	804	
12	Shale	816	
4	Lime	820	
37	Shale	857	
12	Broken Sand	869	Good Show
61	Shale	930	TD