

Form	ACO1 - Well Completion
Operator	RJ Energy, LLC
Well Name	JB GEORGE 14
Doc ID	1835264

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	9.875	7	17	40	portland	5	
Production	5.625	2.875	6.5	897	portland	120	

RJ Energy, LLC

Drill Log - Cement Log

Lease:	JB George	Start:	12/30/2024	Surface:	7 "	40 '	5 Sacks
Well#	14	Finish:	12/31/2024				
API#	15-207-30025			Longstring:	2.875 "	897 '	120 Sacks

Span	Formation	Depth	Notes	
4	Top Soil	4		Pumped 120 sacks and circulated to the top using company tools.
16	Clay & Gravel	20		
38	Shale	58		
56	Lime	114		
72	Shale	186		
102	Lime	288		
45	Shale	333		
145	Lime	478		
178	Shale	656		
25	Lime	681		
59	Shale	740		
32	Lime	772		
13	Shale	785		
10	Lime	795		
13	Shale	808		
9	Lime	817		
6	Shale	823		
4	Lime	827		
39	Shale	866		
9	Broken Sand	875	Good Show	
25	Shale	900	TD	