

Form	ACO1 - Well Completion
Operator	RJ Energy, LLC
Well Name	JB GEORGE 23
Doc ID	1850709

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	9.875	7	23	40	portland	8	
Production	5.625	2.875	6.5	902	portland	120	

RJ Energy, LLC

Drill Log - Cement Log

Lease: JB George	Start: 4/28/2025	Surface: 7 " 40 ' 8 Sacks
Well# 23	Finish: 4/29/2025	
API# 15-207-30064		Longstring: 2.875 " 902 ' 120 Sacks

Span	Formation	Depth	Notes
4	Top Soil	4	Pumped 120 sacks and circulated to the top using company tools.
20	Clay & Gravel	24	
30	Shale	54	
65	Lime	119	
71	Shale	190	
110	Lime	300	
36	Shale	336	
140	Lime	476	
189	Shale	665	
10	Lime	675	
64	Shale	739	
30	Lime	769	
13	Shale	782	
11	Lime	793	
11	Shale	804	
7	Lime	811	
10	Shale	821	
3	Lime	824	
39	Shale	863	
6	Broken Sand	869	Good Show
43	Shale	912	TD