

Form	ACO1 - Well Completion
Operator	RJ Energy, LLC
Well Name	JB GEORGE 17
Doc ID	1850708

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	9.875	7	23	40	portland	8	
Production	5.625	2.875	6.5	919	portland	120	

RJ Energy, LLC

Drill Log - Cement Log

Lease: JB George	Start: 4/25/2025	Surface: 7 " 40 ' 8 Sacks
Well# 17	Finish: 4/28/2025	
API# 15-207-30077		Longstring: 2.875 " 919 ' 120 Sacks

Span	Formation	Depth	Notes
4	Top Soil	4	Pumped 120 sacks and circulated to the top using company tools.
20	Clay & Gravel	24	
34	Shale	58	
39	Lime	97	
93	Shale	190	
102	Lime	292	
46	Shale	338	
140	Lime	478	
187	Shale	665	
10	Lime	675	
65	Shale	740	
30	Lime	770	
12	Shale	782	
12	Lime	794	
12	Shale	806	
8	Lime	814	
9	Shale	823	
3	Lime	826	
42	Shale	868	
7	Broken Sand	875	Good Show
55	Shale	930	TD