

Form	ACO1 - Well Completion
Operator	RJ Energy, LLC
Well Name	JB GEORGE 15
Doc ID	1850701

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	9.875	7	23	40	portland	8	
Production	5.625	2.875	6.5	905	portland	120	

RJ Energy, LLC

Drill Log - Cement Log

Lease: JB George	Start: 4/14/2025	Surface: 7 " 40 ' 8 Sacks
Well# 15	Finish: 4/15/2025	
API# 15-207-30022		Longstring: 2.875 " 905 ' 120 Sacks

Span	Formation	Depth	Notes
4	Top Soil	4	Pumped 120 sacks and circulated to the top using company tools.
120	Clay & Gravel	124	
-53	Shale	71	
54	Lime	125	
59	Shale	184	
105	Lime	289	
41	Shale	330	
142	Lime	472	
193	Shale	665	
10	Lime	675	
63	Shale	738	
30	Lime	768	
15	Shale	783	
9	Lime	792	
10	Shale	802	
8	Lime	810	
12	Shale	822	
3	Lime	825	
39	Shale	864	
11	Broken Sand	875	Good Show
40	Shale	915	TD