

Form	ACO1 - Well Completion
Operator	RJ Energy, LLC
Well Name	WOLFE MCADAM 13W
Doc ID	1850698

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	9.875	7	23	40	portland	8	
Production	5.625	2.875	6.5	883	portland	120	

RJ Energy, LLC

Drill Log - Cement Log

Lease:	Wolf McAdam	Start:	4/9/2025	Surface:	7 "	40 '	8 Sacks
Well#	13W	Finish:	4/10/2025	Longstring:	2.875 "	883 '	120 Sacks
API#	15-207-30053	Waste:	4/12/2025	Perfs:	860 '	870 '	

Span	Formation	Depth	Notes
4	Top Soil	4	Pumped 120 sacks and circulated to the top using company tools.
18	Clay & Gravel	22	
39	Shale	61	
50	Lime	111	
71	Shale	182	
100	Lime	282	
41	Shale	323	
145	Lime	468	
196	Shale	664	
10	Lime	674	
60	Shale	734	
32	Lime	766	
12	Shale	778	
7	Lime	785	
14	Shale	799	
5	Lime	804	
11	Shale	815	
3	Lime	818	
40	Shale	858	
12	Broken Sand	870	Good Show
23	Shale	893	TD