

Form	ACO1 - Well Completion
Operator	RJ Energy, LLC
Well Name	JB GEORGE 18W
Doc ID	1850674

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	9.875	7	23	40	portland	8	
Production	5.625	2.875	6.5	894	portland	120	

RJ Energy, LLC

Drill Log - Cement Log

Lease:	JB George	Start:	4/3/2025	Surface:	7 "	40 '	8 Sacks
Well#	18W	Finish:	4/4/2025				
API#	15-207-30067			Longstring:	2.875 "	894 '	120 Sacks

Span	Formation	Depth	Notes
4	Top Soil	4	Pumped 120 sacks and circulated to the top using company tools.
20	Clay & Gravel	24	
39	Shale	63	
45	Lime	108	
83	Shale	191	
98	Lime	289	
45	Shale	334	
146	Lime	480	
184	Shale	664	
10	Lime	674	
65	Shale	739	
31	Lime	770	
14	Shale	784	
12	Lime	796	
12	Shale	808	
4	Lime	812	
10	Shale	822	
3	Lime	825	
40	Shale	865	
7	Broken Sand	872	
58	Shale	930	TD