

Form	ACO1 - Well Completion
Operator	RJ Energy, LLC
Well Name	WOLFE MCADAM 10W
Doc ID	1850663

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	9.875	7	23	40	portland	8	
Production	5.625	2.875	6.5	891	portland	120	

RJ Energy, LLC

Drill Log - Cement Log

Lease: Wolf McAdam	Start: 3/17/2025	Surface: 7 " 40 ' 8 Sacks
Well# 10W	Finish: 3/19/2025	
API# 15-207-30005		Longstring: 2.875 " 891 ' 120 Sacks

Span	Formation	Depth	Notes
4	Top Soil	4	Pumped 120 sacks and circulated to the top using company tools.
18	Clay & Gravel	22	
50	Shale	72	
47	Lime	119	
77	Shale	196	
90	Lime	286	
41	Shale	327	
140	Lime	467	
196	Shale	663	
10	Lime	673	
60	Shale	733	
31	Lime	764	
14	Shale	778	
10	Lime	788	
12	Shale	800	
6	Lime	806	
10	Shale	816	
3	Lime	819	
40	Shale	859	
8	Broken Sand	867	Good Show
33	Shale	900	TD