KOLAR Document ID: 1851711

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form CP-111
July 2017
Form must be Typed
Form must be signed
All blanks must be complete

TEMPORARY ABANDONMENT WELL APPLICATION

OPERATOR: License# 32446
Name: Merit Energy Company, LLC
Address 1: 13727 Noel Road, Suite 1200
Address 2:
City: Dallas State: TX Zip: 75240 + 7362
Contact Person: Idania Medina
Phone: (972) 628-1446
Contact Person Email: idania.medina@meritenergy.com
Field Contact Person: Nic Hernandez
Field Contact Person Phone: (620) 353-9358

API No. 15- 15-081-21620-00-00
Spot Description:
__ - __ - NE - SW Sec. 30 Twp. 30 S. R. 33 ☐ E ☑ W
2000 feet from ☐ N / ☑ S Line of Section
1997 feet from ☐ E / ☑ W Line of Section
GPS Location: Lat: (e.g. xx.xxxxx) , Long: (e.g. -xxx.xxxxx)
Datum: ☐ NAD27 ☐ NAD83 ☐ WGS84
County: Haskell Elevation: 2951 ☐ GL ☐ KB
Lease Name: Stalker ET AL Well #: 30-K30-30-33
Well Type: *(check one)* ☐ Oil ☑ Gas ☐ OG ☐ WSW ☐ Other:
☐ SWD Permit #: ☐ ENHR Permit #:
☐ Gas Storage Permit #:
Spud Date: 10/05/2005 Date Shut-In: 11/01/2015

	Conductor	Surface	Production	Intermediate	Liner	Tubing
Size	N/A	8.625	5.5	N/A	N/A	2.375
Setting Depth		1670	5301			5208
Amount of Cement		725	275			N/A
Top of Cement		0	0			N/A
Bottom of Cement		1670	5301			N/A

Casing Fluid Level from Surface: 5132 How Determined? echometer Date: 07/08/2025
Casing Squeeze(s): ___ (top) to ___ (bottom) w / ___ sacks of cement, ___ (top) to ___ (bottom) w / ___ sacks of cement. Date:
Do you have a valid Oil & Gas Lease? ☑ Yes ☐ No
Depth and Type: ☐ Junk in Hole at ___ (depth) ☐ Tools in Hole at ___ (depth) Casing Leaks: ☐ Yes ☐ No Depth of casing leak(s):
Type Completion: ☑ ALT. I ☐ ALT. II Depth of: ☐ DV Tool: ___ (depth) w / ___ sacks of cement ☐ Port Collar: ___ (depth) w / ___ sack of cement
Packer Type: Size: Inch Set at: Feet
Total Depth: 5570 Plug Back Depth: 5288 Plug Back Method: Cmt

Geological Date:

Formation Name	Formation Top	Formation Base	Completion Information
1. Morrow	At:	to Feet	Perforation Interval 5103 to 5158 Feet or Open Hole Interval to Feet
2.	At:	to Feet	Perforation Interval to Feet or Open Hole Interval to Feet

UNDER PENALTY OF PERJURY I HEREBY ATTEST THAT THE INFORMATION CONTAINED HEREIN IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE

Submitted Electronically


***Do NOT Write in This Space* - KCC USE ONLY**
Date Tested: Results: Date Plugged: Date Repaired: Date Put Back in Service:
Review Completed by: Michael Maier Comments:
TA Approved: ☑ Yes ☐ Denied Date: 07/17/2025

Mail to the Appropriate KCC Conservation Office:




KCC District Office #1 - 210 E. Frontview, Suite A, Dodge City, KS 67801	Phone 620.682.7933
KCC District Office #2 - 3450 N. Rock Road, Building 600, Suite 601, Wichita, KS 67226	Phone 316.337.7400
KCC District Office #3 - 137 E. 21st St., Chanute, KS 66720	Phone 620.902.6450
KCC District Office #4 - 2301 E. 13th Street, Hays, KS 67601-2651	Phone 785.261.6250


Group: SUBLETTE Well: Stalker 30K (acquired on: 07/08/25 09:30:05)



Filter Type	High Pass		Automatic Collar Count	Yes	Time	8.188 sec
Manual Acoustic Velo	1248.03 ft/s		Manual JTS/sec	19.685	Joints	161.886 Jts
					Depth	5131.77 ft


[1.0 to 2.0 (Sec)]





Analysis Method: Automatic

Group: SUBLETTE Well: Stalker 30K (acquired



Change in Pressure	-0.33	psi
Change in Time	1.00	min

Group: SUBLETTE Well: Stalker 30K (acquired on: 07/08/25 09:30:05)

Production	Current	Potential	
Oil	- * -	- * -	BBL/D
Water	- * -	- * -	BBL/D
Gas	- * -	- * -	Mscf/D

IPR Method	Vogel	
PBHP/SBHP	- * -	
Production Efficiency	0.0	
Oil	40	deg.API
Water	1.05	Sp.Gr.H2O
Gas	0.72	Sp.Gr.AIR
Acoustic Velocity	1253.49	ft/s

Casing Pressure	290.3 psi (g)
Casing Pressure Buildup	-0.333 psi
	1.00 min
Gas/Liquid Interface Pressure	332.2 psi (g)
Liquid Level Depth	5131.77 ft
Pump Intake Depth	5167.00 ft
Formation Depth	5103.00 ft



Producing

Annular Gas Flow 0 Mscf/D

% Liquid 100 %

Formation Submergence		
Total Gaseous Liquid Column HT (TVD)	35	ft
Equivalent Gas Free Liquid HT (TVD)	35	ft


Pump Intake 343.9 psi (g)

Producing BHP 332.0 psi (g)

Static BHP - * - psi (g)

7/8/25

Group: SUBLETTE Well: Stalker 30K (acquired



Acoustic Velocity	1253.49	ft/s	Joints counte
Joints Per Second	19.7711	jts/sec	Joints to liqu
Depth to liquid level	5131.77	ft	Filter Width
Automatic Collar Count	Yes		Time to 1st (

Conservation Division
District Office No. 1
210 E. Frontview, Suite A
Dodge City, KS 67801

Kansas
Corporation Commission

Phone: 620-682-7933
http://kcc.ks.gov/

Andrew J. French, Chairperson
Dwight D. Keen, Commissioner
Annie Kuether, Commissioner

Laura Kelly, Governor

07/17/2025

Idania Medina
Merit Energy Company, LLC
13727 Noel Road, Suite 1200
Dallas, TX 75240-7362

Re: Temporary Abandonment
API 15-081-21620-00-00
Stalker ET AL 30-K30-30-33
SW/4 Sec.30-30S-33W
Haskell County, Kansas

Dear Idania Medina:

"Your temporary abandonment (TA) application for the well listed above has been approved. In accordance with K.A.R. 82-3-111 the TA status of this well will expire 11/01/2025.

* If you return this well to service or plug it, please notify the District Office.

* If you sell this well you are required to file a Transfer of Operator form, T-1.

* If the well will remain temporarily abandoned, you must submit a new TA application, CP-111, before 11/01/2025.

You may contact me at the number above if you have questions.

Very truly yours,

Michael Maier"