

Form	ACO1 - Well Completion
Operator	Colorado Interstate Gas Co., LLC
Well Name	CPS 1072 B1 1
Doc ID	1859298

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	16	10.750	7.5	20	Bentonite	16	0



new groundbed

tie new groundbed
junction box into old
groundbed junction box
positive cable



2025 Well Logs for CPS 1072

Elkhart 2025 Project Hole #1 - CPS 1072

North Hole: N 37.183029 W 102.026875

0-3 Topsoil

3-18 Fine medium sand and clay

18-26 Rock

26-40 Tan clay and fine sand streaks

40-60 Brown clay and fine sand streaks

60-110 Fine medium sand with brown clay streaks

110-120 Red clay shale and fine sand streaks

120-140 Red Tan clay shale and fine sand streaks

140-160 Tan, brown clay rock streak layers and sandstone

160-235 Tan, red sandstone

Elkhart 2025 Project Hole #2 - CPS 1072

South Hole N 37.182970 W 102.026852

0-3 Topsoil

3-20 Fine medium sand and tan clay

20-24 Rock

24-80 Brown clay and fine coarse sand

80-110 Fine coarse sand with tan, red clay

110-130 Tan, red clay and rock with sandstone

130-160 Tan, brown, reddish clay rock streak layers and sandstone

160-235 Tan, red sandstone