KOLAR Document ID: 1859856

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form CP-111
July 2017
Form must be Typed
Form must be signed
All blanks must be complete

TEMPORARY ABANDONMENT WELL APPLICATION

OPERATOR: License# 4706
Name: Messenger Petroleum, Inc.
Address 1: 525 S MAIN ST
Address 2:
City: KINGMAN State: KS Zip: 67068 + 1968
Contact Person: Jon F. Messenger
Phone: (620) 532-5400
Contact Person Email:
Field Contact Person:
Field Contact Person Phone: ( )

API No. 15- 15-095-21174-00-00
Spot Description:
NE SW NW NW Sec. 6 Twp. 30 S. R. 6 ☐ E ☑ W
930 feet from ☑ N / ☐ S Line of Section
400 feet from ☐ E / ☑ W Line of Section
GPS Location: Lat: (e.g. xx.xxxxx) , Long: (e.g. -xxx.xxxxx)
Datum: ☐ NAD27 ☐ NAD83 ☐ WGS84
County: Kingman Elevation: ☐ GL ☐ KB
Lease Name: CLARK Well #: 1
Well Type: *(check one)* ☑ Oil ☐ Gas ☐ OG ☐ WSW ☐ Other:
☐ SWD Permit #: ☐ ENHR Permit #:
☐ Gas Storage Permit #:
Spud Date: 10/13/1981 Date Shut-In: 10/04/2019

	Conductor	Surface	Production	Intermediate	Liner	Tubing
Size	NA	8.625	5.50	NA	NA	2.375
Setting Depth		259	4140			4110
Amount of Cement		200	200			NA
Top of Cement		0	NA			NA
Bottom of Cement		259	4140			NA

Casing Fluid Level from Surface: 2475 How Determined? Echometer Date: 09/07/2025
Casing Squeeze(s): (top) to (bottom) w / sacks of cement, (top) to (bottom) w / sacks of cement. Date:
Do you have a valid Oil & Gas Lease? ☑ Yes ☐ No
Depth and Type: ☐ Junk in Hole at (depth) ☐ Tools in Hole at (depth) Casing Leaks: ☐ Yes ☐ No Depth of casing leak(s):
Type Completion: ☑ ALT. I ☐ ALT. II Depth of: ☐ DV Tool: (depth) w / sacks of cement ☐ Port Collar: (depth) w / sack of cement
Packer Type: Size: Inch Set at: Feet
Total Depth: 4141 Plug Back Depth: 4125 Plug Back Method: cement

Geological Date:

Formation Name	Formation Top	Formation Base	Completion Information
1. Miss	At:	to Feet	Perforation Interval 4098 to 4102 Feet or Open Hole Interval to Feet
2.	At:	to Feet	Perforation Interval to Feet or Open Hole Interval to Feet

UNDER PENALTY OF PERJURY I HEREBY ATTEST THAT THE INFORMATION CONTAINED HEREIN IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE

Submitted Electronically

***Do NOT Write in This Space* - KCC USE ONLY**

Date Tested:	Results:	Date Plugged:	Date Repaired:	Date Put Back in Service:


Review Completed by: Neil Lake, ECRS Comments: TA good for 1-year
TA Approved: ☑ Yes ☐ Denied Date: 09/22/2025

Mail to the Appropriate KCC Conservation Office:




KCC District Office #1 - 210 E. Frontview, Suite A, Dodge City, KS 67801	Phone 620.682.7933
KCC District Office #2 - 3450 N. Rock Road, Building 600, Suite 601, Wichita, KS 67226	Phone 316.337.7400
KCC District Office #3 - 137 E. 21st St., Chanute, KS 66720	Phone 620.902.6450
KCC District Office #4 - 2301 E. 13th Street, Hays, KS 67601-2651	Phone 785.261.6250

Group: MyWells Well: Clark 1 (acquired on: 09/07/25 19:01:40)



Time 3.811 sec
Joints 78.0834 Jts
Depth 2475.24 ft




Liquid level calculated with
user supplied Acoustic Velocity

Acoustic Velocity 1299 ft/s

Analysis Method: Acoustic Velocity

Group: MyWells Well: Clark 1 (acquired on: 09/07/25 19:01:40)



Change in Pressure 0.00 psi
Change in Time 1.25 min

PT4091
Range 0 - ? psi

Group: MyWells Well: Clark 1 (acquired on: 09/07/25 19:01:40)

Production
Current Potential
Oil 1.5 - * - BBL/D
Water 95 - * - BBL/D
Gas 5.0 - * - Mscf/D

IPR Method Vogel
PBHP/SBHP - * -
Production Efficiency 0.0

Oil 40 deg.API
Water 1.05 Sp.Gr.H2O
Gas 0.71 Sp.Gr.AIR

Acoustic Velocity 1299 ft/s


Formation Submergence
Total Gaseous Liquid Column HT (TVD) 1630 ft
Equivalent Gas Free Liquid HT (TVD) 1630 ft

Acoustic Test

Casing Pressure
-0.0 psi (g)
Casing Pressure Buildup
0.002 psi
1.25 min
Gas/Liquid Interface Pressure
0.9 psi (g)

Liquid Level Depth
2475.24 ft

Pump Intake Depth
4105.00 ft
Formation Depth
4098.00 ft



Producing

Annular
Gas Flow
0 Mscf/D
% Liquid
100 %

Pump Intake
546.5 psi (g)
Producing BHP
544.3 psi (g)
Static BHP
- * - psi (g)

Group: MyWells Well: Clark 1 (acquired on: 09/07/25 19:01:40)

Entered Acoustic Velocity for Liquid Level depth determination

Conservation Division
District Office No. 2
3450 N. Rock Road
Building 600, Suite 601
Wichita, KS 67226

Kansas
Corporation Commission

Phone: 316-337-7400
http://kcc.ks.gov/

Andrew J. French, Chairperson
Dwight D. Keen, Commissioner
Annie Kuether, Commissioner

Laura Kelly, Governor

09/22/2025

Jon F. Messenger
Messenger Petroleum, Inc.
525 S MAIN ST
KINGMAN, KS 67068-1968

Re: Temporary Abandonment
API 15-095-21174-00-00
CLARK 1
NW/4 Sec.06-30S-06W
Kingman County, Kansas

Dear Jon F. Messenger:

"Your temporary abandonment (TA) application for the well listed above has been approved. In accordance with K.A.R. 82-3-111 the TA status of this well will expire 09/22/2026.

* If you return this well to service or plug it, please notify the District Office.

* If you sell this well you are required to file a Transfer of Operator form, T-1.

* If the well will remain temporarily abandoned, you must submit a new TA application, CP-111, before 09/22/2026.

You may contact me at the number above if you have questions.

Very truly yours,

Neil Lake, ECRS"