

Form	ACO1 - Well Completion
Operator	Colt Energy Inc
Well Name	Lipsey 26
Doc ID	1731754

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	12.25	8.625	24	40	H325	30	None
Production	6.75	4.5	10.5	1019	Thixotropic	125	2#/sx phenoseal

Colt Energy Driller's Log														
Lease: Lipsey			Well No. 26		Well Location: 2158' FSL & 1668' FWL			Sec. 2		Twp. 23S		Rng. 16E		
API #: 15-031-24667			Type: Oil		County: Coffey			State: KS		Spud Date: 8/16/23		Total Depth: 1035'		
Driller: Pat Stewart			Surface Casing		Bit Record				Coring Record					
Crew: Dan Foust			Bit Size:	12.25"	Type	Size	Start	End	Core #	Size		Start	End	
			Casing Size:	8.625"	PDC	12.25"	0	40'	1					
Start Rig Hrs:			Casing Length:	40'	PDC	6.75"	40'	1035'	2					
End Rig Hrs:			Cement Used:	30 sx					3					
Total Rig Hrs:			Cement Type:	H325					4					
From	To	Formation			From	To	Formation			4 1/2" Casing Tally				
0	24	Overburden/shale			844	852	Limestone			1	40.00		19	44.50
24	30	River Gravel			852	872	Shale			2	43.60		20	42.10
30	144	Shale			872	874	Limestone			3	43.70		21	42.60
144	214	Limestone			874	890	Shale			4	43.60		22	43.20
214	318	Shale			890	918	Limestone			5	43.60		23	43.00
318	330	Limestone			918	966	Shale			6	40.20		24	42.80
330	346	Shale			966	974	Sandstone			7	43.30		25	
346	422	Limestone			974	1035	Shale			8	40.20		26	
422	472	Shale								9	43.60		27	
472	532	Limestone								10	41.10		28	
532	540	Shale								11	41.20		29	
540	562	Limestone								12	41.00		30	
562	568	Shale								13	41.00		31	
568	586	Limestone								14	41.00		32	
586	722	Shale								15	43.20		33	
722	730	Limestone								16	41.10		34	
730	774	Shale								17	44.70		35	
774	783	Limestone								18	41.00		36	
783	844	Shale								Total: 1015.3' + 4' shoe= 1019.3'				