

Form	ACO1 - Well Completion
Operator	S & K Oil Production, Inc.
Well Name	MCKINNIS 17
Doc ID	1735301

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	9.875	7	6	20	one	5	0
Production	5.875	2.875	6	719	one	81	0

McGOWN

DRILLING, INC.

Mound City, KS

620.224.7406

Well #				Casing			
S&K Oil Production Inc. McKinnis 17				Surface		Longstring	
				Size:	7 "	Size:	2 7/8 "
API #: 15-011-24764 S-T-R:				Tally:	20.0 '	Tally:	719.0 '
County: Bourbon Date: 9/25/2023				Cement:	5 sx	Bit:	5 7/8 "
				Bit:	9 7/8 "	Date:	9/26/2023

Top	Base	Formation	Top	Base	Formation
0	2	soil	454	480	shale
2	7	clay & gravel	480	494	lime
7	69	lime	494	505	shale
69	72	blk shale	505	509	lime
72	74	lime	509	650	shale
74	80	shale	650	659	blk sand no odor
80	119	lime	659	673	shale
119	123	blk shale	673	688	white sandy shale
123	127	lime	688	709	sand slight odor, slight bleed in sa
127	131	shale	709	710	coal
131	146	lime	710		sandy shale
146	148	shale	Cemented by S&K Oil Prod 81 SXS.		
148	149	lime			
149	169	shale			
169	188	lime			
188	189	shale			
189	191	lime	Float Equipment		
191	300	shale			
300	306	lime			
306	311	shale			
311	312	lime			
312	322	shale	Qty	Size	
			1	2 7/8	Float Shoe
			3	2 7/8	Centralizers
			1	2 7/8	Casing clamp
#REF!	322		Sand / Core Detail		
322	326	lime			
326	335	shale			
335	338	lime			
338	441	shale			
441	343	red bed	688	690	slight odor, slight bleed in samples
343	350	shale	690	692	good odor, fair bleed in samples
350	359	sand grey	692	694	good odor, good bleed in samples
359	409	sandy shale	694	698	good odor, fair bleed in samples
409	411	lime	698	702	good odor, good bleed to pit, soft
411	416	shale	702	709	blk sand, slight odot, no bleed
416	434	lime			
434	451	shale			
451	454	lime			
Total Depth:			722		