

Form	ACO1 - Well Completion
Operator	RJ Energy, LLC
Well Name	WHETSTONE 2A
Doc ID	1864653

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	9.875	7	17	20	portland	8	
Production	5.625	2.875	6.5	846	portland	100	

RJ Energy, LLC

Drill Log - Cement Log

Lease: Whetstone	Start: 6/26/2025	Surface: 7 " 20 ' 8 Sacks
Well# 2A	Finish: 6/27/2025	Longstring: 2.875 " 846 ' 100 Sacks
API# 15-003-27226	Waste: 6/29/2025	Perfs 784 ' 794 '
		Perfs: 795 ' 805 '

Span	Formation	Depth	Notes
1	Top Soil	1	
4	Clay & Gravel	5	
31	Lime	36	
160	Shale	196	
33	Sandy Shale	229	
62	Lime	291	
108	Shale	399	
180	Lime	579	
20	Shale	599	
61	Lime	660	
28	Shale	688	
21	Lime	709	
6	Shale	715	
17	Lime	732	
8	Shale	740	
7	Lime	747	
11	Shale	758	
16	Lime	774	
4	Shale	778	Odor
36	Black Sand	814	Good Show
2	Black Sand	816	Show
54	Shale	870	TD

Pumped 100 sacks
and circulated to the top
using company tools.

