

Form	ACO1 - Well Completion
Operator	RJ Energy, LLC
Well Name	WHETSTONE 1W
Doc ID	1864652

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	9.875	7	17	20	portland	8	
Production	5.625	2.875	6.5	806	portland	100	

RJ Energy, LLC

Drill Log - Cement Log

Lease: Whetstone	Start: 6/24/2025	Surface: 7 " 20 ' 8 Sacks
Well# 1W	Finish: 6/25/2025	Longstring: 2.875 " 806 ' 100 Sacks
API# 15-003-27223	Waste: 6/27/2025	Perfs 767 ' 777 '

Span	Formation	Depth	Notes	
1	Top Soil	1	Pumped 100 sacks and circulated to the top using company tools.	
4	Clay & Gravel	5		
25	Lime	30		
154	Shale	184		
28	Sandy Shale	212		
62	Lime	274		
105	Shale	379		
181	Lime	560		
21	Shale	581		
63	Lime	644		
30	Shale	674		
15	Lime	689		
6	Shale	695		
23	Lime	718		
4	Shale	722		
8	Lime	730		
5	Shale	735		
15	Lime	750		
14	Shale	764		Odor
14	Black Sand	778		Good Show
62	Shale	840	TD	

