

Form	ACO1 - Well Completion
Operator	RJ Energy, LLC
Well Name	WHETSTONE 2W
Doc ID	1864654

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	9.875	7	17	20	portland	8	
Production	5.625	2.875	6.5	850	portland	100	

RJ Energy, LLC

Drill Log - Cement Log

Lease: Whetstone	Start: 6/25/2025	Surface: 7 " 20 ' 8 Sacks
Well# 2W	Finish: 6/26/2025	Longstring: 2.875 " 850 ' 100 Sacks
API# 15-003-27227	Waste: 6/28/2025	Perfs 783 ' 793 '
		Perfs: 795 ' 805 '

Span	Formation	Depth	Notes
2	Top Soil	2	Pumped 100 sacks and circulated to the top using company tools.
3	Clay & Gravel	5	
36	Lime	41	
155	Shale	196	
34	Sandy Shale	230	
62	Lime	292	
105	Shale	397	
183	Lime	580	
20	Shale	600	
65	Lime	665	
25	Shale	690	
19	Lime	709	
5	Shale	714	
17	Lime	731	
9	Shale	740	
10	Lime	750	
5	Shale	755	
18	Lime	773	
5	Shale	778	Odor
32	Black Sand	810	Good Show
4	Black Sand	814	Show
46	Shale	860	TD

