

Form	ACO1 - Well Completion
Operator	RJ Energy, LLC
Well Name	WHETSTONE 5A
Doc ID	1864658

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	9.875	7	17	20	portland	8	
Production	5.625	2.875	6.5	842	portland	100	

RJ Energy, LLC

Drill Log - Cement Log

Lease: Whetstone	Start: 7/2/2025	Surface: 7 " 20 ' 8 Sacks
Well# 5A	Finish: 7/3/2025	Longstring: 2.875 " 842 ' 100 Sacks
API# 15-003-27228	Waste: 7/5/2025	Perfs 773 ' 783 '
		Perfs: 784 ' 794 '
		Perfs: 795 ' 805 '

Span	Formation	Depth	Notes	
1	Top Soil	1	Pumped 100 sacks and circulated to the top using company tools.	
2	Clay & Gravel	3		
25	Lime	28		
160	Shale	188		
36	Sandy Shale	224		
56	Lime	280		
105	Shale	385		
185	Lime	570		
18	Shale	588		
62	Lime	650		
30	Shale	680		
16	Lime	696		
5	Shale	701		
19	Lime	720		
7	Shale	727		
6	Lime	733		
4	Shale	737		
20	Lime	757		
11	Shale	768		Odor
38	Black Sand	806		Good Show
4	Black Sand	810	Show	
42	Shale	852	TD	

