

Form	ACO1 - Well Completion
Operator	RJ Energy, LLC
Well Name	WHETSTONE 13W
Doc ID	1864674

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	9.875	7	17	20	portland	8	
Production	5.625	2.875	6.5	818	portland	100	

RJ Energy, LLC

Drill Log - Cement Log

Lease: Whetstone	Start: 7/29/2025	Surface: 7 " 20 ' 8 Sacks
Well# 13W	Finish: 7/30/2025	Longstring: 2.875 " 818 ' 100 Sacks
API# 15-003-27246	Waste: 8/1/2025	Perfs 768 ' 778 '
		Perfs: 781 ' 791 '
		Perfs: 792' 802 '

Span	Formation	Depth	Notes
1	Top Soil	1	Pumped 100 sacks and circulated to the top using company tools.
2	Clay & Gravel	3	
32	Lime	35	
150	Shale	185	
32	Sandy Shale	217	
69	Lime	286	
100	Shale	386	
176	Lime	562	
24	Shale	586	
65	Lime	651	
28	Shale	679	
20	Lime	699	
7	Shale	706	
14	Lime	720	
8	Shale	728	
8	Lime	736	
5	Shale	741	
19	Lime	760	
7	Shale	767	
37	Black Sand	804	Show
3	Black Sand	807	Good Show
33	Shale	840	TD

