

Form	ACO1 - Well Completion
Operator	Castle Resources, Inc.
Well Name	STACKHOUSE OWWO 1
Doc ID	1864272

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	12.25	8.625	20	225	common	150	3%CC2% Gel
Production	7.88	5.5	15.5	3599	80/20	555	60/40

KS Oilfield Service

St., P.O. Box 225, Victoria, KS 67671 ♦ 24 Hour Phone (785) 639-7269

Phone (785) 639-3949

♦ Email: franksoilfield@yahoo.com

TICKET NUMBER

1611

LOCATION

Victoria

FOREMAN

Walt Dinkel

FIELD TICKET & TREATMENT REPORT

CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10-2-25		Stackhouse, owner #1	13	12S	19W	Ellis
CUSTOMER Castle Resources, Inc.			Yocoma #1			
MAILING ADDRESS Box 103			TRUCK #			
CITY			DRIVER			
STATE			TRUCK #			
ZIP CODE			DRIVER			

JOB TYPE Prod HOLE SIZE 7 7/8" HOLE DEPTH 3600' CASING SIZE & WEIGHT 5 1/2" - 15.5#
 CASING DEPTH 3599' DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 110-145 SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 10'
 DISPLACEMENT 91 BBL DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety Meeting, Rig up Equipment, circ casing on bottom
Pump 30 sks in Bitt. mixed 400 sks 60/40 por, 8% Gel, 1/4" Flo Seal, Pumped a
50 BBL mud spacer mixed 125 sks 80/20 por, 10% Salt + 5# Koccol, 20% Gel
Clear Pump + Lines, release Plug and Displaced 91 BBL H₂O @ 900#
Handled Plug @ 1200#, released Pressure Float Held
Cement Drill Core

Thank You
Walt & Eve

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
PC004	1	PUMP CHARGE	\$2500.00	\$2500.00
MO01	25	MILEAGE	\$4.50	\$112.50
MO02	26.39	Ton Mileage Delivery	\$789.62	\$789.62
MO04	25	Pick-up Mileage	\$1.50	\$37.50
CB035	125 - sks	Class 80/20 por, 10% Salt, 5# Koccol, 20% Gel	\$25.00	\$3,125.00
CB021	430 - sks	60/40 por, 8% Gel, 1/4" Flo Seal	\$17.95	\$7,718.50
FE033	1	5 1/2" Flo & Shoe	\$100.00	\$100.00
FE051	1	5 1/2" Latchdown Plug Assy	\$695.00	\$695.00
FE014	5	5 1/2" Centralizers (Turbo)	\$108.00	\$540.00
FE022	1	5 1/2" Basket	\$385.00	\$385.00
FE102	1	5 1/2" Limit Clamp	\$35.00	\$35.00
			sub total	\$14,783.12
			less 10% disc.	\$1,478.31
			sub total	\$13,304.81
			SALES TAX	825.21
			ESTIMATED TOTAL	15934.52

AUTHORIZATION _____

TITLE _____

DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.