

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009

Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: _____
 Name: _____
 Address 1: _____
 Address 2: _____
 City: _____ State: _____ Zip: _____ + _____
 Contact Person: _____
 Phone: (_____) _____
 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - _____
 Spot Description: _____
 _____ - _____ - _____ - _____ Sec. _____ Twp. _____ S. R. _____ East West
 _____ Feet from North / South Line of Section
 _____ Feet from East / West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: _____
 Lease Name: _____ Well #: _____
 Date Well Completed: _____
 The plugging proposal was approved on: _____ (Date)
 by: _____ (KCC District Agent's Name)
 Plugging Commenced: _____
 Plugging Completed: _____

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugging Contractor License #: _____ Name: _____
 Address 1: _____ Address 2: _____
 City: _____ State: _____ Zip: _____ + _____
 Phone: (_____) _____
 Name of Party Responsible for Plugging Fees: _____
 State of _____ County, _____, ss.
 _____ Employee of Operator or Operator on above-described well,
 (Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Submitted Electronically



Gemini Wireline LLC
1023 Reservation Rd
Hays, KS 67601

Invoice

Date	Invoice #
1/8/2026	8628

RECEIVED
JAN 12 2026

BY: _____
Bill To
Edison Operating Company LLC
9342 E Central, Suite A
Wichita, KS 67206

Terms	Lease Name
Net 30	Campbell 8-2

Service Date	Job Ticket	Description	Amount
1/7/2026	6841	Set CIBP	3,650.00

Thank you for your business!		Total	\$3,650.00
Main Office	Fax	Casey Patterson Hays, KS	Jason Cappellucci Liberal, KS
785-625-1182	785-625-1180	785-656-3035	719-680-4158

If you would like to start receiving your invoices via email, please send your contact information to steph@romecorporation.net



**COMANCHE
WELL
SERVICE, LLC**

8100 E 22ND N BLDG 1900: WICHITA, KANSAS 67226

TICKET #

1291

COMPANY

EDISON OPERATING COMPANY

DATE

1/5/26 (Monday)

LEASE NAME:

CAMPBELL

WELL#

8-2

TOTAL HOURS:

10.00

MATERIAL USED:

TOOLS USED:

SWAB CUPS 2-3/8

STANDING VALVE

SWAB CUPS 2-7/8

TUBING TONGS

OIL SAVER RUBBER

ROD TONGS

THREAD DOPE

ROD FISHING TOOL

ROD WIPER RUBBER

TUBING SLIP SEGMENTS

TUBING WIPER RUBBER

SAND PUMP

OPERATOR

MIGUEL ROBLEDO

AIR PACKS

D. MAN S

JUAN JURADO

H2S MONITOR

FLOOR MAN

ARMANDO CHAVEZ

MULTI-GAS MONITOR

LEASE NAME: CAMPBELL

WELL# 8-2

NOTES/JOB TYPE:

drove pulling unit to location, spot in & rig up pulling unit, unhang well, pull pumping unit back, unseat pump, trip out w/ 1-1/8"x 16' pr, 1-3/8"x 6' liner, 1-4' 5/8" rod sub, laydown 112 plain 5/8" rods, 1-1/2"x 1-1/8"x 10 rwbc pump, 6' gas anchor, unplug well head, rig up for 1-1/2" tubing, pull tubing of the slips, trip out & stand back 54 joints of 1-1/2" tubing, laydown rest of tubing 31 joints of 1-1/2" tubing, 1-1/2" seating nipple, 1-1/2"x 10' mud anchor, pack well off, pick up & clean up tubing & rod equipment, shut down for the day.



**COMANCHE
WELL
SERVICE, LLC**

8100 E 22ND N BLDG 1900: WICHITA, KANSAS 67226

TICKET #

1294

COMPANY

EDISON OPERATING COMPANY

DATE

1/7/26 (Wednesday)

LEASE NAME:

CAMPBELL

WELL#

8-2

TOTAL HOURS:

15.00

MATERIAL USED:

TOOLS USED:

SWAB CUPS 2-3/8

STANDING VALVE

SWAB CUPS 2-7/8

TUBING TONGS

X

OIL SAVER RUBBER

ROD TONGS

THREAD DOPE

X

ROD FISHING TOOL

ROD WIPER RUBBER

TUBING SLIP SEGMENTS

TUBING WIPER RUBBER

X

SAND PUMP

OPERATOR

MIGUEL ROBLEDO

AIR PACKS

D. MAN S

JUAN JURADO

H2S MONITOR

FLOOR MAN

GERONIMO OROZCO

MULTI-GAS MONITOR

LEASE NAME:

CAMPBELL

WELL#

8-2

NOTES/JOB TYPE:

Pick up crew drove crew to location, held pre job safety meeting, ccwe, unbolt well head of the sales line & brake well head to be able to get thru w/ cibp, rig up gemini wire line run in the hole w/ cibp & wasn't able to get thru passed 500 feet, flushed casing w/ 30 bbls, set 5-1/2" cibp@2355', dumped 2 sks of cement on cibp, rig down moved out wire line, trip in the hole w/ 55 joints of 1-1/2" tubing to 1815', rig up hsi pumped 30 barrels of cement & displaced 2.5 barrels, laydown 32 joints set end of tbq@750 feet w/ 23 joints, circulate cement out to surface 5-1/2" casing w/ 150 sacks of cement from 750 feet, trip out & laydown 23 joints & top off 5-1/2" casing, rig up hsi on surface pipe & pumped 50 sacks of cement down 8-5/8" psi to 300#, wash up tools, clean up & pick up tubing equipment, secured equipment, rig down pulling unit, clean up trash of location, drove pulling unit to next location & sdfd.



HURRICANE SERVICES INC

Remit To: Hurricane Services, Inc.
250 N. Water, Suite 200
Wichita, KS 67202
316-303-9515

COPY

Customer: EDISON OPERATING CO LLC
9342 E CENTRAL
SUITE A
WICHITA, KS 67206

Invoice Date: 1/7/2026
Invoice #: 0388324
Lease Name: Campbell
Well #: 8-2
County: Kearny, Ks
Job Number: WP6799
District: Oakley

Date/Description	HRS/QTY	Rate	Total
Plug to Abandon	0.000	0.000	0.00
H-Plug	230.000	14.400	3,312.00
Light Eq Mileage	77.000	1.800	138.60
Heavy Eq Mileage	154.000	3.600	554.40
Ton Mileage	762.000	1.350	1,028.70
Cement Pump Service	1.000	675.000	675.00
Cement Blending & Mixing	230.000	1.260	289.80
Depth Charge 1001'-2000'	1.000	1,350.000	1,350.00
Service Supervisor	1.000	247.500	247.50

Net Invoice 7,596.00
Sales Tax: 450.47
Total 8,046.47

TERMS: Net 30 days. Interest may be charged on past due invoice at rate of 1 ½% per month or maximum allowed by applicable state or federal laws. HSI has right to revoke any discounts applied in arriving at net invoice price if invoice is past due. If revoked, full invoice price without discount plus additional sales tax, as applicable, is due immediately and subject to interest charges. Customer agrees to pay all collection costs directly or indirectly incurred by HSI in the event HSI engages a third party to pursue collection of past due invoice.

SALES TAX: Services performed on oil, gas and water wells in Kansas are subject to sales tax, with certain exceptions. HSI relies on the well information provided by the customer in identifying whether the services performed on wells qualify for exemption.

WE APPRECIATE YOUR BUSINESS!

