

WATER WELL RECORD (WWC5.2)

Constructed

KOLAR DOC ID 1970424

WELL ID

LOCATION OF WATER WELL

County	Ellis	Section	29	Township	13	Range	18 ☐ E ☒ W	Fraction	NE ¼ SW ¼ SW ¼
Latitude	38.8883	Longitude	-99.35243	Datum	WGS84	Elevation	2005		

WATER WELL LOCATION☐ at owner's address1200feet NE of 27th Street and Hiway 183 Bypass
Hays, KS 67601**WATER WELL OWNER**

Name	Donald Tillman
Business	
Address	2748 Thunderbird Circle Hays KS 67601-1644

PERMIT & ID NUMBERS (AS REQUIRED)

DWR Application No.: _____
 KDHE / EPA Project Code: _____
 Site Name: _____
 KDHE UIC Class V Form Completed: ☐ Yes ☐ No
 County/Local Permit Required? ☐ Yes ☐ No
 Permit Obtained? ☒ Yes ☐ No Permit ID: ELWW2516
 Oil/Gas Lease Name & Well #: _____

CONSTRUCTION

Casing: Height above land surface: 36 in.
 Is casing height less than 12 inches? ☐ Yes ☒ No
 Blank Casing type: ThermalPlastic
 1st interval: 0 ft. to 20 ft.; Diameter 5 in.
 Casing Joint: : Glued Weight: _____ lbs/ft
 Wall thickness or gauge no.: SDR26
 2nd interval: _____ ft. to _____ ft.; Diameter _____ in.
 Casing Joint: : _____ Weight: _____ lbs/ft
 Wall thickness or gauge no.: _____
 3rd interval: _____ ft. to _____ ft.; Diameter _____ in.
 Casing Joint: : _____ Weight: _____ lbs/ft
 Wall thickness or gauge no.: _____

Screen / Perforation material: PVC

Specify if other: _____

Screen / Perforation openings: Mill slot

1st interval 20 ft. to 54 ft. Slot Size .025 inches

2nd interval _____ ft. to _____ ft. Slot Size _____

3rd interval _____ ft. to _____ ft. Slot Size _____

WELL WATER USE

Domestic Household

Additional info if required:

of Boreholes

of Dewatering Wells

COMPLETION

Depth of completed well: 54 ft.

Depth(s) groundwater encountered: ☐ Dry Well

(1) 20 ft.; (2) _____ ft.; (3) _____ ft.;

Static water level in well: 32 ft.

Date measured: 06/14/2026

Measured from: ☐ Top of Casing or ☒ Ground SurfaceMeasured: ☐ Above or ☒ Below Land Surface

Estimated yield: 50 gpm

Pump Test Date: Water level was:

32 ft. after 2 hours pumping 10 gpm

_____ ft. after _____ hours pumping _____ gpm

Pump Information:Pump Installed? ☐ Yes ☒ No Date:

Pump Type: Horsepower: Volts:

Drop Pipe Diameter: in. Drop Pipe Length: ft.

Water well disinfected? ☒ Yes ☐ No

Date disinfected (mm/dd/yy): 06/14/2026

CONSTRUCTION**Borehole interval:**

from 0 to 54 ft.

from _____ to _____ ft.

from _____ to _____ ft..

Borehole diameter:

10 in.

_____ in.

_____ in.

Grout:

1st Interval: 0 ft. to 20 ft. Grout material: Bentonite

2nd Interval: _____ ft. to _____ ft. Grout material: _____

3rd Interval: _____ ft. to _____ ft. Grout material: _____

Gravel pack:1st Interval: 20 ft. to 48 ft. Gravel Size: 3/8 ☐ Not Used2nd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐3rd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐**DESIGNATED PERSON** Dale Meder**WELL COMPLETION DATE** 06/13/2026**CONTRACTOR BUSINESS NAME** M&M Water Well Service

