

WATER WELL RECORD (WWC5.2)

Constructed

KOLAR DOC ID 1975398

WELL ID

LOCATION OF WATER WELL

County	Chase	Section	24	Township	20	Range	9	☒ E ☐ W	Fraction	SW ¼	SW ¼	NW ¼
Latitude	38.296807	Longitude	-96.373618	Datum	WGS84	Elevation	1360					

WATER WELL LOCATION☐ at owner's address

Well is located 1.5 miles north of the Yy Rd/I-35 overpass and 60-feet east of Yy Rd.

WATER WELL OWNER

Name	
Business	Footo Cattle Company
Address	PO Box 11
	Bucyrus KS 66013

PERMIT & ID NUMBERS (AS REQUIRED)

DWR Application No.: _____
 KDHE / EPA Project Code: _____
 Site Name: _____
 KDHE UIC Class V Form Completed: ☐ Yes ☐ No
 County/Local Permit Required? ☐ Yes ☐ No
 Permit Obtained? ☐ Yes ☒ No Permit ID: _____
 Oil/Gas Lease Name & Well #: _____

CONSTRUCTION

Casing: Height above land surface: 12 in.
 Is casing height less than 12 inches? ☐ Yes ☒ No
 Blank Casing type: ThermalPlastic
 1st interval: 0 ft. to 60 ft.; Diameter 6 in.
 Casing Joint: : Glued Weight: _____ lbs/ft
 Wall thickness or gauge no.: SCH40
 2nd interval: 100 ft. to 140 ft.; Diameter 6 in.
 Casing Joint: : Glued Weight: _____ lbs/ft
 Wall thickness or gauge no.: SCH40
 3rd interval: _____ ft. to _____ ft.; Diameter _____ in.
 Casing Joint: : _____ Weight: _____ lbs/ft
 Wall thickness or gauge no.: _____

Screen / Perforation material: PVC

Specify if other: _____

Screen / Perforation openings: Mill slot1st interval 60 ft. to 100 ft. Slot Size .032 inches

2nd interval _____ ft. to _____ ft. Slot Size _____

3rd interval _____ ft. to _____ ft. Slot Size _____

WELL WATER USE

Domestic Livestock/Pasture

Additional info if required:

of Boreholes

of Dewatering Wells

COMPLETIONDepth of completed well: 140 ft.Depth(s) groundwater encountered: ☐ Dry Well(1) 39 ft.; (2) 72 ft.; (3) _____ ft.;Static water level in well: 61 ft.Date measured: 07/06/2026Measured from: ☐ Top of Casing or ☒ Ground SurfaceMeasured: ☐ Above or ☒ Below Land SurfaceEstimated yield: 12 gpm

Pump Test Date: Water level was:

_____ ft. after _____ hours pumping _____ gpm

_____ ft. after _____ hours pumping _____ gpm

Pump Information:Pump Installed? ☐ Yes ☒ No Date: _____

Pump Type: _____ Horsepower: _____ Volts: _____

Drop Pipe Diameter: _____ in. Drop Pipe Length: _____ ft.

Water well disinfected? ☒ Yes ☐ NoDate disinfected (mm/dd/yy): 07/06/2026**CONSTRUCTION****Borehole interval:**from 0 to 140 ft.

from _____ to _____ ft.

from _____ to _____ ft..

Borehole diameter:10 in.

_____ in.

_____ in.

Grout:1st Interval: 0 ft. to 24 ft. Grout material: Bentonite2nd Interval: 110 ft. to 112 ft. Grout material: Bentonite

3rd Interval: _____ ft. to _____ ft. Grout material: _____

Gravel pack:

Not Used

1st Interval: 24 ft. to 110 ft. Gravel Size: _____ ☐2nd Interval: 112 ft. to 140 ft. Gravel Size: _____ ☐3rd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐**DESIGNATED PERSON** Kyler Erickson**WELL COMPLETION DATE** 07/06/2026**CONTRACTOR BUSINESS NAME** Associated Drilling, Inc. #990

WATER WELL RECORD (WWC-5)

Constructed

KOLAR DOC ID 1975398 WELL ID _____

LOCATION OF WATER WELL

County	Chase	Section	24	Township	20	Range	9	</
--------	-------	---------	----	----------	----	-------	---	---

NEAREST SOURCE OF POTENTIAL CONTAMINATION or ☒ No potential source of contamination within 100 ft.

Source:	Source:
Distance from well (ft):	Distance from well (ft):
Direction from well:	Direction from well:
Source description:	Source description:
Required information for local entity? ☐ Yes ☐ No	Required information for local entity? ☐ Yes ☐ No

LITHOLOGIC LOG**AQUIFER, if known** Flint Hills

FROM	TO	LITHOLOGY
0	1	topsoil
1	3	limestone,unweathered
3	4	shale,unweathered
4	7	limestone,unweathered
7	19	shale,unweathered
19	39	limestone,unweathered
39	42	limestone,moderately weathered
42	50	limestone,unweathered
50	51	limestone,moderately weathered
51	55	limestone,unweathered
55	56	limestone,moderately weathered
56	66	limestone,unweathered
66	72	limestone,moderately weathered
72	94	shale,moderately weathered
94	127	shale,unweathered
127	140	shaley limestone,unweathered

COMMENTS

This water well was constructed ☐ reconstructed pursuant to the stated water well contractor's license and was completed on 07/06/2026 .

I certify that this record is true to the best of my knowledge and belief. This water well record was completed on 07/21/2026 under the business name of Associated Drilling, Inc. #990 , KS Water Well Contractor's License No. 990 under the authority of the designated person as defined in K.A.R. 28-30-2(j) and signed and certified by the electronic signature of the designated person at its submittal: **Kyler Erickson** . Send one copy to the water well owner and the contractor should retain one copy.