

WATER WELL RECORD (WWC5.2)

Constructed

KOLAR DOC ID 1972247

WELL ID _____

LOCATION OF WATER WELL

County	Nemaha	Section	10	Township	5	Range	12 ☒ E ☐ W	Fraction	NE ¼ NE ¼ NE ¼
Latitude	39.63667	Longitude	-96.05284	Datum	WGS84	Elevation	1304		

WATER WELL LOCATION☐ at owner's address

595 K Rd
Corning, KS 66417

WATER WELL OWNER

Name	Dan Rempe
Business	
Address	6512 Atlantic St Corning KS 66417

PERMIT & ID NUMBERS (AS REQUIRED)

DWR Application No.: _____
 KDHE / EPA Project Code: _____
 Site Name: _____
 KDHE UIC Class V Form Completed: ☐ Yes ☐ No
 County/Local Permit Required? ☐ Yes ☐ No
 Permit Obtained? ☐ Yes ☒ No Permit ID: _____
 Oil/Gas Lease Name & Well #: _____

CONSTRUCTION

Casing: Height above land surface: 24 in.
 Is casing height less than 12 inches? ☐ Yes ☒ No
 Blank Casing type: ThermalPlastic
 1st interval: 0 ft. to 250 ft.; Diameter 6 in.
 Casing Joint: : Splines Weight: _____ lbs/ft
 Wall thickness or gauge no.: SDR17
 2nd interval: 270 ft. to 290 ft.; Diameter 6 in.
 Casing Joint: : Splines Weight: _____ lbs/ft
 Wall thickness or gauge no.: SDR17
 3rd interval: _____ ft. to _____ ft.; Diameter _____ in.
 Casing Joint: : _____ Weight: _____ lbs/ft
 Wall thickness or gauge no.: _____

Screen / Perforation material: PVC

Specify if other: _____

Screen / Perforation openings: Mill slot

1st interval 250 ft. to 270 ft. Slot Size .032 inches

2nd interval _____ ft. to _____ ft. Slot Size _____

3rd interval _____ ft. to _____ ft. Slot Size _____

WELL WATER USE

Domestic Livestock/Pasture

Additional info if required:

of Boreholes _____ # of Dewatering Wells _____

COMPLETION

Depth of completed well: 290 ft.

Depth(s) groundwater encountered: ☐ Dry Well

(1) 254 ft.; (2) _____ ft.; (3) _____ ft.;

Static water level in well: 100 ft.

Date measured: 07/09/2026

Measured from: ☐ Top of Casing or ☒ Ground SurfaceMeasured: ☐ Above or ☒ Below Land Surface

Estimated yield: 30 gpm

Pump Test Date: Water level was:

_____ ft. after _____ hours pumping _____ gpm

_____ ft. after _____ hours pumping _____ gpm

Pump Information:Pump Installed? ☐ Yes ☒ No Date: _____

Pump Type: _____ Horsepower: _____ Volts: _____

Drop Pipe Diameter: _____ in. Drop Pipe Length: _____ ft.

Water well disinfected? ☒ Yes ☐ No

Date disinfected (mm/dd/yy): 07/09/2026

CONSTRUCTION**Borehole interval:**

from 0 to 290 ft.

from _____ to _____ ft.

from _____ to _____ ft..

Borehole diameter:

10 in.

_____ in.

_____ in.

Grout:

1st Interval: 0 ft. to 23 ft. Grout material: Bentonite

2nd Interval: _____ ft. to _____ ft. Grout material: _____

3rd Interval: _____ ft. to _____ ft. Grout material: _____

Gravel pack:

Not Used

1st Interval: 23 ft. to 290 ft. Gravel Size: _____ ☐2nd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐3rd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐**DESIGNATED PERSON** Kyler Erickson**WELL COMPLETION DATE** 07/09/2026**CONTRACTOR BUSINESS NAME** Associated Drilling, Inc. #990

WATER WELL RECORD (WWC-5)

Constructed

KOLAR DOC ID 1972247 WELL ID _____

LOCATION OF WATER WELL

County	Nemaha	Section	10	Township	5	Range	12	
--------	--------	---------	----	----------	---	-------	----	--

NEAREST SOURCE OF POTENTIAL CONTAMINATION or ☒ No potential source of contamination within 100 ft.

Source:	Source:
Distance from well (ft):	Distance from well (ft):
Direction from well:	Direction from well:
Source description:	Source description:
Required information for local entity? ☐ Yes ☐ No	Required information for local entity? ☐ Yes ☐ No

LITHOLOGIC LOG**AQUIFER, if known** Glacial Drift

FROM	TO	LITHOLOGY
0	25	clay,tan
25	48	clay,gray
48	53	gravel,fine
53	71	clay,blue
71	78	sand,coarse
78	107	clay,blue
107	110	gravel,fine
110	134	clay,gravelly,blue
134	151	clay,blue
151	153	gravel,fine
153	237	clay,blue
237	254	clay,gravelly,blue
254	263	gravel,medium
263	290	shale,unweathered,gray

COMMENTS

This water well was constructed ☐ reconstructed pursuant to the stated water well contractor's license and was completed on 07/09/2026 .

I certify that this record is true to the best of my knowledge and belief. This water well record was completed on 07/21/2026 under the business name of Associated Drilling, Inc. #990 , KS Water Well Contractor's License No. 990 under the authority of the designated person as defined in K.A.R. 28-30-2(j) and signed and certified by the electronic signature of the designated person at its submittal: Kyler Erickson . Send one copy to the water well owner and the contractor should retain one copy.