

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4

March 2009

Type or Print on this Form

Form must be Signed

All blanks must be Filled

OPERATOR: License #: 36231
Name: Tradewater Well Services, LLC
Address 1: 650 MORSE AVENUE
Address 2: _____
City: ELK GROVE VILLAGE State: IL Zip: 60007 + 5102
Contact Person: Kirsten Dueck
Phone: (312) 940-3968
Type of Well: (Check one) ☐ Oil Well ☒ Gas Well ☐ OG ☐ D&A ☐ Cathodic
☐ Water Supply Well ☐ Other: _____ ☐ SWD Permit #: _____
☐ ENHR Permit #: _____ ☐ Gas Storage Permit #: _____
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No
Producing Formation(s): List All (If needed attach another sheet)
Wabaunsee Depth to Top: 2860 Bottom: 2868 T.D. _____
Topeka Depth to Top: 3147 Bottom: 3159 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 15-129-10298-00-01
Spot Description: _____
E2 W2 NE NW Sec. 24 Twp. 33 S. R. 42 ☐ East ☒ West
4620 Feet from ☐ North / ☒ South Line of Section
3343 Feet from ☒ East / ☐ West Line of Section
Footages Calculated from Nearest Outside Section Corner:
☐ NE ☐ NW ☒ SE ☐ SW
County: Morton
Lease Name: YODER Well #: 1-24
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Plugging Commenced: 7/17/2026
Plugging Completed: 7/22/2026

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8.625	597	0
		Production	5.5	3205	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 3100' w/ 10 sx cement on top
Set CIBP @ 2810', circulate w/ 66 bbls mud and cap plug w/ 10 sx cement
Spot 50 sx cement w/ 2% CaCl and 100 lbs hulls @ 1500', WOC and tag TOC @ 1185'
Spot 30 sx cement @ 630'
Spot 20 sx cement w/ 2% CaCl and hulls @ 64' cement to surface
Tie on to 8-5/8" and pump 25 sx cement w/ 2% CaCl to 500 psi

Plugging Contractor License #: 36050 Name: Orr Energy Services LLC
Address 1: PO BOX 389 Address 2: _____
City: ENID State: OK Zip: 73702 + 0389
Phone: (580) 237-6152
Name of Party Responsible for Plugging Fees: Tradewater Well Services, LLC
State of _____ County, _____, ss.

(Print Name) ☐ Employee of Operator or ☐ Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Submitted Electronically