

WATER WELL RECORD (WWC5.2)

Constructed

KOLAR DOC ID 1970643

WELL ID _____

LOCATION OF WATER WELL

County	Bourbon	Section	1	Township	27	Range	25 ☒ E ☐ W	Fraction	NW ¼ SE ¼ NW ¼
Latitude	37.727319	Longitude	-94.626724	Datum	WGS84	Elevation	869		

WATER WELL LOCATION☐ at owner's address

2632 Dustyt Road Garland, KS

WATER WELL OWNER

Name David Vanlerberg

Business

Address 6929 Martindale Rd
Shawnee KS 66218

PERMIT & ID NUMBERS (AS REQUIRED)

DWR Application No.: _____

KDHE / EPA Project Code: _____

Site Name: _____

KDHE UIC Class V Form Completed: ☐ Yes ☐ No

County/Local Permit Required? ☐ Yes ☐ No

Permit Obtained? ☐ Yes ☐ No Permit ID: _____

Oil/Gas Lease Name & Well #: _____

CONSTRUCTION

Casing: Height above land surface: 12 in.
Is casing height less than 12 inches? ☐ Yes ☒ No

Blank Casing type: ThermalPlastic

1st interval: 0 ft. to 42 ft.; Diameter 6 in.
Casing Joint: : Glued Weight: _____ lbs/ft
Wall thickness or gauge no.: SCH 40

2nd interval: 0 ft. to 560 ft.; Diameter 4 in.
Casing Joint: : Glued Weight: _____ lbs/ft
Wall thickness or gauge no.: SCH 40

3rd interval: _____ ft. to _____ ft.; Diameter _____ in.
Casing Joint: : _____ Weight: _____ lbs/ft
Wall thickness or gauge no.: _____

Screen / Perforation material: PVC

Specify if other: _____

Screen / Perforation openings: Continuous slot (PVC)

1st interval 560 ft. to 620 ft. Slot Size _____

2nd interval _____ ft. to _____ ft. Slot Size _____

3rd interval _____ ft. to _____ ft. Slot Size _____

WELL WATER USE

Domestic Lawn/Garden

Additional info if required:

of Boreholes _____ # of Dewatering Wells _____

COMPLETION

Depth of completed well: 620 ft.

Depth(s) groundwater encountered: ☐ Dry Well

(1) _____ ft.; (2) _____ ft.; (3) _____ ft.;

Static water level in well: 240 ft.

Date measured: 06/26/2026

Measured from: ☒ Top of Casing or ☐ Ground SurfaceMeasured: ☐ Above or ☒ Below Land Surface

Estimated yield: 110 gpm

Pump Test Date: Water level was:

320 ft. after 12 hours pumping 100 gpm

_____ ft. after _____ hours pumping _____ gpm

Pump Information:Pump Installed? ☒ Yes ☐ No Date: _____

Pump Type: _____ Horsepower: _____ Volts: _____

Drop Pipe Diameter: 2 in. Drop Pipe Length: _____ ft.

Water well disinfected? ☒ Yes ☐ No

Date disinfected (mm/dd/yy): 06/26/2026

CONSTRUCTION**Borehole interval:**

from 0 to 42 ft.

from 42 to 620 ft.

from _____ to _____ ft..

Borehole diameter:

10 in.

6 in.

_____ in.

Grout:

1st Interval: 0 ft. to 42 ft. Grout material: Bentonite

2nd Interval: _____ ft. to _____ ft. Grout material: _____

3rd Interval: _____ ft. to _____ ft. Grout material: _____

Gravel pack:

Not Used

1st Interval: _____ ft. to _____ ft. Gravel Size: _____ ☒2nd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐3rd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐**DESIGNATED PERSON** Matty Yoakum**WELL COMPLETION DATE** 06/26/2026**CONTRACTOR BUSINESS NAME**

Matty Yoakum-Yoakum Well Drilling & Pump Co

WATER WELL RECORD (WWC-5)

Constructed

KOLAR DOC ID 1970643 WELL ID _____

LOCATION OF WATER WELL

County	Bourbon	Section	1	Township	27	Range	25	<
--------	---------	---------	---	----------	----	-------	----	--

NEAREST SOURCE OF POTENTIAL CONTAMINATION or ☒ No potential source of contamination within 100 ft.

Source:	Source:
Distance from well (ft):	Distance from well (ft):
Direction from well:	Direction from well:
Source description:	Source description:
Required information for local entity? ☐ Yes ☐ No	Required information for local entity? ☐ Yes ☐ No

LITHOLOGIC LOG**AQUIFER, if known**

FROM	TO	LITHOLOGY
0	5	clay,tan
5	10	clay,sandy,tan,hard
10	65	shale,unweathered
65	120	limestone,unweathered,hard,w/ thin shale strips
120	380	shale,unweathered,w/ a few limestone strips
380	560	limestone,unweathered,whiteish,gray,very hard,gray chert
560	580	limestone,unweathered,very hard,chert-yield great increases
580	620	limestone,unweathered,white,very hard,bright white chert-yielded the most

COMMENTS

Shale trap at 520', 420', 55'.

This water well was constructed ☐ reconstructed pursuant to the stated water well contractor's license and was completed on 06/26/2026 .

I certify that this record is true to the best of my knowledge and belief. This water well record was completed on 06/27/2026 under the business name of Matty Yoakum-Yoakum Well Drilling & P, KS Water Well Contractor's License No. 100E under the authority of the designated person as defined in K.A.R. 28-30-2(j) and signed and certified by the electronic signature of the designated person at its submittal: Matty Yoakum . Send one copy to the water well owner and the contractor should retain one copy.