

WATER WELL RECORD (WWC5.2)

Constructed

KOLAR DOC ID 1976102

WELL ID _____

LOCATION OF WATER WELL

County	Stevens	Section	28	Township	32	Range	36 ☐ E ☒ W	Fraction	NE ¼ NW ¼ NE ¼
Latitude	37.241528	Longitude	-101.235205	Datum	WGS84	Elevation	3072		

WATER WELL LOCATION☐ at owner's address

From intersection of RD T and RD 19 0.254 mile west
360 ft south

WATER WELL OWNER

Name	Bryne Sullins
Business	B&T Farms
Address	1973 Rd T Mscow Ks KS 67952

PERMIT & ID NUMBERS (AS REQUIRED)

DWR Application No.: _____
 KDHE / EPA Project Code: _____
 Site Name: _____
 KDHE UIC Class V Form Completed: ☐ Yes ☐ No
 County/Local Permit Required? ☐ Yes ☐ No
 Permit Obtained? ☐ Yes ☒ No Permit ID: _____
 Oil/Gas Lease Name & Well #: _____

CONSTRUCTION

Casing: Height above land surface: 12 in.
 Is casing height less than 12 inches? ☐ Yes ☒ No
 Blank Casing type: ThermalPlastic
 1st interval: 0 ft. to 360 ft.; Diameter 5 in.
 Casing Joint: : Glued Weight: _____ lbs/ft
 Wall thickness or gauge no.: SDR17
 2nd interval: _____ ft. to _____ ft.; Diameter _____ in.
 Casing Joint: : _____ Weight: _____ lbs/ft
 Wall thickness or gauge no.: _____
 3rd interval: _____ ft. to _____ ft.; Diameter _____ in.
 Casing Joint: : _____ Weight: _____ lbs/ft
 Wall thickness or gauge no.: _____

Screen / Perforation material: PVC

Specify if other: _____

Screen / Perforation openings: Continuous slot (PVC)1st interval 360 ft. to 560 ft. Slot Size _____

2nd interval _____ ft. to _____ ft. Slot Size _____

3rd interval _____ ft. to _____ ft. Slot Size _____

WELL WATER USE

Domestic Livestock/Pasture

Additional info if required:

of Boreholes

of Dewatering Wells

COMPLETIONDepth of completed well: 560 ft.Depth(s) groundwater encountered: ☐ Dry Well

(1) _____ ft.; (2) _____ ft.; (3) _____ ft.;

Static water level in well: 260 ft.Date measured: 07/10/2026Measured from: ☒ Top of Casing or ☐ Ground SurfaceMeasured: ☐ Above or ☒ Below Land Surface

Estimated yield: _____ gpm

Pump Test Date: Water level was:

_____ ft. after _____ hours pumping _____ gpm

_____ ft. after _____ hours pumping _____ gpm

Pump Information:Pump Installed? ☐ Yes ☒ No Date: _____

Pump Type: _____ Horsepower: _____ Volts: _____

Drop Pipe Diameter: _____ in. Drop Pipe Length: _____ ft.

Water well disinfected? ☐ Yes ☐ No

Date disinfected (mm/dd/yy): _____

CONSTRUCTION**Borehole interval:**from 0 to 560 ft.

from _____ to _____ ft.

from _____ to _____ ft..

Borehole diameter:10 in.

_____ in.

_____ in.

Grout:1st Interval: 5 ft. to 25 ft. Grout material: Bentonite

2nd Interval: _____ ft. to _____ ft. Grout material: _____

3rd Interval: _____ ft. to _____ ft. Grout material: _____

Gravel pack:

Not Used

1st Interval: 25 ft. to 560 ft. Gravel Size: _____ ☐2nd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐3rd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐**DESIGNATED PERSON** Blain Marshall**WELL COMPLETION DATE** 07/10/2026**CONTRACTOR BUSINESS NAME** B & M Services SWK, LLC

WATER WELL RECORD (WWC-5)

Constructed

KOLAR DOC ID 1976102 WELL ID _____

LOCATION OF WATER WELL

County	Stevens	Section	28	Township	32	Range	36	E W Fraction	NE	¼	NW	¼	NE	¼
Latitude	37.241528	Longitude	-101.235205			Datum		WGS84	Elevation		3072			
Well Owner	Bryne	Sullins			Well Owner Business			B&T Farms						

NEAREST SOURCE OF POTENTIAL CONTAMINATION or ☒ No potential source of contamination within 100 ft.

Source:	Source:
Distance from well (ft):	Distance from well (ft):
Direction from well:	Direction from well:
Source description:	Source description:
Required information for local entity? ☐ Yes ☐ No	Required information for local entity? ☐ Yes ☐ No

LITHOLOGIC LOG**AQUIFER, if known**

FROM	TO	LITHOLOGY
0	3	topsoil
3	20	sand,fine,clayey
20	160	clay,brownish
160	280	sand & gravel,fine to medium
280	300	sand,fine
300	320	clay,brownish
320	540	sand & gravel,fine to medium
540	560	clay,brownish
560	570	clay,red

COMMENTS

This water well was constructed ☐ reconstructed pursuant to the stated water well contractor's license and was completed on **07/10/2026**.

I certify that this record is true to the best of my knowledge and belief. This water well record was completed on **08/07/2026** under the business name of **B & M Services SWK, LLC**, KS Water Well Contractor's License No. **1072** under the authority of the designated person as defined in K.A.R. 28-30-2(j) and signed and certified by the electronic signature of the designated person at its submittal: **Blain Marshall**. Send one copy to the water well owner and the contractor should retain one copy.