

WATER WELL RECORD (WWC5.2)

Constructed

KOLAR DOC ID 1981345

WELL ID _____

LOCATION OF WATER WELL

County	Trego	Section	23	Township	12	Range	22 ☐ E ☒ W	Fraction	SE ¼ SE ¼ SW ¼
Latitude	38.987041	Longitude	-99.733451	Datum	WGS84	Elevation	2361		

WATER WELL LOCATION☐ at owner's address

In Trego county, in Ogallah from Walnut St and Century St. 1159' S and 90' west

WATER WELL OWNER

Name	Justin Choitz
Business	
Address	2502 Indian Trail
	Hays Kar 67601

PERMIT & ID NUMBERS (AS REQUIRED)

DWR Application No.: _____

KDHE / EPA Project Code: _____

Site Name: _____

KDHE UIC Class V Form Completed: ☐ Yes ☐ No

County/Local Permit Required? ☐ Yes ☐ No

Permit Obtained? ☒ Yes ☐ No Permit ID: 1205

Oil/Gas Lease Name & Well #: _____

CONSTRUCTION

Casing: Height above land surface: 24 in.

Is casing height less than 12 inches? ☐ Yes ☒ No

Blank Casing type: ThermalPlastic

1st interval: 0 ft. to 91 ft.; Diameter 5 in.

Casing Joint: : Glued Weight: 200 lbs/ft

Wall thickness or gauge no.: SDR21

2nd interval: _____ ft. to _____ ft.; Diameter _____ in.

Casing Joint: : _____ Weight: _____ lbs/ft

Wall thickness or gauge no.: _____

3rd interval: _____ ft. to _____ ft.; Diameter _____ in.

Casing Joint: : _____ Weight: _____ lbs/ft

Wall thickness or gauge no.: _____

Screen / Perforation material: PVC

Specify if other: _____

Screen / Perforation openings: Saw cut1st interval 91 ft. to 111 ft. Slot Size _____

2nd interval _____ ft. to _____ ft. Slot Size _____

3rd interval _____ ft. to _____ ft. Slot Size _____

WELL WATER USE

Domestic Household

Additional info if required:

of Boreholes

of Dewatering Wells

COMPLETIONDepth of completed well: 111 ft.Depth(s) groundwater encountered: ☐ Dry Well

(1) _____ ft.; (2) _____ ft.; (3) _____ ft.;

Static water level in well: 72 ft.Date measured: 08/05/2026Measured from: ☒ Top of Casing or ☐ Ground SurfaceMeasured: ☐ Above or ☒ Below Land SurfaceEstimated yield: 30 gpm

Pump Test Date: Water level was:

_____ ft. after _____ hours pumping _____ gpm

_____ ft. after _____ hours pumping _____ gpm

Pump Information:Pump Installed? ☐ Yes ☒ No Date: _____

Pump Type: _____ Horsepower: _____ Volts: _____

Drop Pipe Diameter: _____ in. Drop Pipe Length: _____ ft.

Water well disinfected? ☒ Yes ☐ NoDate disinfected (mm/dd/yy): 08/05/2026**CONSTRUCTION****Borehole interval:**from 0 to 111 ft.

from _____ to _____ ft.

from _____ to _____ ft..

Borehole diameter:10 in.

_____ in.

_____ in.

Grout:1st Interval: 0 ft. to 28 ft. Grout material: Bentonite

2nd Interval: _____ ft. to _____ ft. Grout material: _____

3rd Interval: _____ ft. to _____ ft. Grout material: _____

Gravel pack:

Not Used

1st Interval: 28 ft. to 111 ft. Gravel Size: _____ ☐2nd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐3rd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐**DESIGNATED PERSON** Keith Pfannenstiel**WELL COMPLETION DATE** 08/05/2026**CONTRACTOR BUSINESS NAME** KP Hydrotech

WATER WELL RECORD (WWC-5)

Constructed

KOLAR DOC ID 1981345 WELL ID _____

LOCATION OF WATER WELL

County	Trego	Section	23	Township	12	Range	22	E W Fraction	SE ¼	SE ¼	SW ¼
Latitude	38.987041	Longitude	-99.733451			Datum	WGS84	Elevation	2361		
Well Owner	Justin	Choitz			Well Owner Business						

NEAREST SOURCE OF POTENTIAL CONTAMINATION or ☒ No potential source of contamination within 100 ft.

Source:	Source:
Distance from well (ft):	Distance from well (ft):
Direction from well:	Direction from well:
Source description:	Source description:
Required information for local entity? ☐ Yes ☐ No	Required information for local entity? ☐ Yes ☐ No

LITHOLOGIC LOG**AQUIFER, if known**

FROM	TO	LITHOLOGY
0	2	topsoil
2	34	clay,brown
34	37	sand,fine
37	39	other,chert
39	50	clay,streaks of chert
50	68	clay,tan
68	72	sand & gravel,fine to coarse
72	81	clay,tan
81	98	clay,sand streaks
98	101	clay,tan
101	111	shale,unweathered

COMMENTS

This water well was constructed ☐ reconstructed pursuant to the stated water well contractor's license and was completed on 08/05/2026 .

I certify that this record is true to the best of my knowledge and belief. This water well record was completed on 09/02/2026 under the business name of KP Hydrotech , KS Water Well Contractor's License No. 478 under the authority of the designated person as defined in K.A.R. 28-30-2(j) and signed and certified by the electronic signature of the designated person at its submittal: Keith Pfannenstiel . Send one copy to the water well owner and the contractor should retain one copy.