

WATER WELL RECORD (WWC5.2)

Constructed

KOLAR DOC ID 1979019

WELL ID _____

LOCATION OF WATER WELL

County	Woodson	Section	17	Township	24	Range	15 ☒ E ☐ W	Fraction	SW ¼ NW ¼ NE ¼
Latitude	37.964438	Longitude	-95.785165	Datum	WGS84	Elevation	1105		

WATER WELL LOCATION☐ at owner's address

from the intersection of jay rd and 170 appx 1 mile east
then 1/8 mile south in pasture

WATER WELL OWNER

Name	jonas schwartz
Business	
Address	1645 jay Rd yates center ks 66783

PERMIT & ID NUMBERS (AS REQUIRED)

DWR Application No.: _____
 KDHE / EPA Project Code: _____
 Site Name: _____
 KDHE UIC Class V Form Completed: ☐ Yes ☐ No
 County/Local Permit Required? ☐ Yes ☐ No
 Permit Obtained? ☐ Yes ☒ No Permit ID: _____
 Oil/Gas Lease Name & Well #: _____

CONSTRUCTION

Casing: Height above land surface: 18 in.
 Is casing height less than 12 inches? ☐ Yes ☒ No
 Blank Casing type: ThermalPlastic
 1st interval: 0 ft. to 106 ft.; Diameter 5 in.
 Casing Joint: : Glued Weight: 40 lbs/ft
 Wall thickness or gauge no.: sdr2100
 2nd interval: _____ ft. to _____ ft.; Diameter _____ in.
 Casing Joint: : _____ Weight: _____ lbs/ft
 Wall thickness or gauge no.: _____
 3rd interval: _____ ft. to _____ ft.; Diameter _____ in.
 Casing Joint: : _____ Weight: _____ lbs/ft
 Wall thickness or gauge no.: _____

Screen / Perforation material: PVC

Specify if other: _____

Screen / Perforation openings: Mill slot1st interval 106 ft. to 126 ft. Slot Size .025 inches

2nd interval _____ ft. to _____ ft. Slot Size _____

3rd interval _____ ft. to _____ ft. Slot Size _____

WELL WATER USE

Domestic Household

Additional info if required:

of Boreholes

of Dewatering Wells

COMPLETIONDepth of completed well: 126 ft.Depth(s) groundwater encountered: ☐ Dry Well(1) 112 ft.; (2) _____ ft.; (3) _____ ft.;Static water level in well: 90 ft.Date measured: 07/30/2026Measured from: ☐ Top of Casing or ☒ Ground SurfaceMeasured: ☐ Above or ☒ Below Land SurfaceEstimated yield: 2 gpm

Pump Test Date: Water level was:

_____ ft. after _____ hours pumping _____ gpm

_____ ft. after _____ hours pumping _____ gpm

Pump Information:Pump Installed? ☐ Yes ☒ No Date: _____

Pump Type: _____ Horsepower: _____ Volts: _____

Drop Pipe Diameter: _____ in. Drop Pipe Length: _____ ft.

Water well disinfected? ☒ Yes ☐ NoDate disinfected (mm/dd/yy): 07/30/2026**CONSTRUCTION****Borehole interval:**from 0 to 126 ft.

from _____ to _____ ft.

from _____ to _____ ft..

Borehole diameter:8 in.

_____ in.

_____ in.

Grout:1st Interval: 0 ft. to 23 ft. Grout material: Cement

2nd Interval: _____ ft. to _____ ft. Grout material: _____

3rd Interval: _____ ft. to _____ ft. Grout material: _____

Gravel pack:

Not Used

1st Interval: 23 ft. to 126 ft. Gravel Size: 1/4 ☐2nd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐3rd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐**DESIGNATED PERSON** Travis Euler**WELL COMPLETION DATE** 07/30/2026**CONTRACTOR BUSINESS NAME** Euler Water Well Drilling

WATER WELL RECORD (WWC-5)

Constructed

KOLAR DOC ID 1979019 WELL ID _____

LOCATION OF WATER WELL

County	Woodson	Section	17	Township	24	Range	15	<
--------	---------	---------	----	----------	----	-------	----	--

NEAREST SOURCE OF POTENTIAL CONTAMINATION or ☒ No potential source of contamination within 100 ft.

Source:	Source:
Distance from well (ft):	Distance from well (ft):
Direction from well:	Direction from well:
Source description:	Source description:
Required information for local entity? ☐ Yes ☐ No	Required information for local entity? ☐ Yes ☐ No

LITHOLOGIC LOG**AQUIFER, if known**

FROM	TO	LITHOLOGY
0	3	loam,very fine,dark,brownish,brown,dry,firm
3	8	clay,very fine,light,yellowish,brown,slightly moist,loose
8	11	sandstone,unweathered,sandy,light,yellowish,red,soft
11	40	shale,unweathered,light,grayish,gray,soft
40	45	shale,unweathered,dark,reddish,red,very soft,sticky
45	60	limestone,unweathered,very light,whiteish,white,hard
60	77	shale,unweathered,light,grayish,gray,soft
77	85	sandstone,unweathered,sandy,light,grayish,gray,soft
85	97	shale,unweathered,light,grayish,gray,soft
97	105	shale,unweathered,sandy,very light,grayish,gray,soft
105	110	shale,unweathered,very dark,blackish,black,hard
110	112	shale,unweathered,dark,grayish,gray,soft
112	126	sandstone,unweathered,sandy,very light,grayish,gray,soft

COMMENTS

This water well was constructed ☐ reconstructed pursuant to the stated water well contractor's license and was completed on 07/30/2026 .

I certify that this record is true to the best of my knowledge and belief. This water well record was completed on 09/03/2026 under the business name of Euler Water Well Drilling , KS Water Well Contractor's License No. 975 under the authority of the designated person as defined in K.A.R. 28-30-2(j) and signed and certified by the electronic signature of the designated person at its submittal: Travis Euler . Send one copy to the water well owner and the contractor should retain one copy.