

WATER WELL RECORD (WWC5.2)

Constructed

KOLAR DOC ID 1981900

WELL ID WELL #4

LOCATION OF WATER WELL

County	Pottawatomie	Section	18	Township	9	Range	12 ☒ E ☐ W	Fraction	NE ¼ NW ¼ SE ¼
Latitude	39.266158	Longitude	-96.116704	Datum	WGS84	Elevation	1229		

WATER WELL LOCATION☐ at owner's address

Well is located in a pasture 2200-feet north of the intersection of Diamond Rd and Pleasant View Rd, then 1780-feet west.

WATER WELL OWNER

Name	
Business	Carlson Old Fashioned Farms
Address	6750 Pleasant View Rd St Marys KS 66536

PERMIT & ID NUMBERS (AS REQUIRED)

DWR Application No.: _____
 KDHE / EPA Project Code: _____
 Site Name: _____
 KDHE UIC Class V Form Completed: ☐ Yes ☐ No
 County/Local Permit Required? ☐ Yes ☐ No
 Permit Obtained? ☐ Yes ☒ No Permit ID: _____
 Oil/Gas Lease Name & Well #: _____

CONSTRUCTION

Casing: Height above land surface: 24 in.
 Is casing height less than 12 inches? ☐ Yes ☒ No
 Blank Casing type: ThermalPlastic
 1st interval: 0 ft. to 70 ft.; Diameter 6 in.
 Casing Joint: : Glued Weight: _____ lbs/ft
 Wall thickness or gauge no.: SCH40
 2nd interval: 90 ft. to 105 ft.; Diameter 6 in.
 Casing Joint: : Glued Weight: _____ lbs/ft
 Wall thickness or gauge no.: SCH40
 3rd interval: _____ ft. to _____ ft.; Diameter _____ in.
 Casing Joint: : _____ Weight: _____ lbs/ft
 Wall thickness or gauge no.: _____

Screen / Perforation material: PVC

Specify if other: _____

Screen / Perforation openings: Mill slot

1st interval 70 ft. to 90 ft. Slot Size .032 inches

2nd interval _____ ft. to _____ ft. Slot Size _____

3rd interval _____ ft. to _____ ft. Slot Size _____

WELL WATER USE

Domestic Livestock/Pasture

Additional info if required:

of Boreholes

of Dewatering Wells

COMPLETION

Depth of completed well: 105 ft.

Depth(s) groundwater encountered: ☐ Dry Well

(1) 73 ft.; (2) _____ ft.; (3) _____ ft.;

Static water level in well: 69 ft.

Date measured: 08/26/2026

Measured from: ☐ Top of Casing or ☒ Ground SurfaceMeasured: ☐ Above or ☒ Below Land Surface

Estimated yield: 26 gpm

Pump Test Date: Water level was:

_____ ft. after _____ hours pumping _____ gpm

_____ ft. after _____ hours pumping _____ gpm

Pump Information:Pump Installed? ☒ Yes ☐ No Date: 09/02/2026

Pump Type: Solar Horsepower: _____ Volts: 80

Drop Pipe Diameter: 1 in. Drop Pipe Length: 97 ft.

Water well disinfected? ☒ Yes ☐ No

Date disinfected (mm/dd/yy): 08/26/2026

CONSTRUCTION**Borehole interval:**

from 0 to 105 ft.

from _____ to _____ ft.

from _____ to _____ ft..

Borehole diameter:

10 in.

_____ in.

_____ in.

Grout:

1st Interval: 0 ft. to 20 ft. Grout material: Bentonite

2nd Interval: 40 ft. to 45 ft. Grout material: Bentonite

3rd Interval: _____ ft. to _____ ft. Grout material: _____

Gravel pack:

Not Used

1st Interval: 20 ft. to 40 ft. Gravel Size: _____ ☐2nd Interval: 45 ft. to 105 ft. Gravel Size: _____ ☐3rd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐**DESIGNATED PERSON** Kyler Erickson**WELL COMPLETION DATE** 08/26/2026**CONTRACTOR BUSINESS NAME** Associated Drilling, Inc. #990

WATER WELL RECORD (WWC-5)

Constructed

KOLAR DOC ID 1981900 WELL ID WELL #4

LOCATION OF WATER WELL

County	Pottawatomie	Section	18	Township	9	Range	12	</
--------	--------------	---------	----	----------	---	-------	----	---

NEAREST SOURCE OF POTENTIAL CONTAMINATION or ☒ No potential source of contamination within 100 ft.

Source:	Source:
Distance from well (ft):	Distance from well (ft):
Direction from well:	Direction from well:
Source description:	Source description:
Required information for local entity? ☐ Yes ☐ No	Required information for local entity? ☐ Yes ☐ No

LITHOLOGIC LOG**AQUIFER, if known** Flint Hills

FROM	TO	LITHOLOGY
0	4	clay,gray
4	15	shale,unweathered,gray
15	34	limestone,unweathered
34	39	shale,unweathered,gray
39	69	shale,unweathered,red
69	72	shaley limestone,unweathered
72	78	limestone,moderately weathered
78	89	shale,unweathered,gray
89	105	shale,unweathered,limestone lenses

COMMENTS

This water well was constructed ☐ reconstructed pursuant to the stated water well contractor's license and was completed on 08/26/2026 .

I certify that this record is true to the best of my knowledge and belief. This water well record was completed on 09/08/2026 under the business name of Associated Drilling, Inc. #990 , KS Water Well Contractor's License No. 990 under the authority of the designated person as defined in K.A.R. 28-30-2(j) and signed and certified by the electronic signature of the designated person at its submittal: Kyler Erickson . Send one copy to the water well owner and the contractor should retain one copy.