

WATER WELL RECORD (WWC5.2)

Constructed

KOLAR DOC ID 1977032

WELL ID _____

LOCATION OF WATER WELL

County	Grant	Section	31	Township	28	Range	37 ☐ E ☒ W	Fraction	NW ¼ NW ¼ NE ¼
Latitude	37.575086	Longitude	-101.4074	Datum	NAD83	Elevation	3080		

WATER WELL LOCATION☐ at owner's address

ULYSSES,KS: WEST ON HWY 160 FOR 2 MILES TO
CO RD H, SOUTH .3 MILE, WEST INTO

WATER WELL OWNER

Name	
Business	SKYLAND GRAIN
Address	1125 W OKLAHOMA
	ULYSSES KS 67880

PERMIT & ID NUMBERS (AS REQUIRED)

DWR Application No.: _____
 KDHE / EPA Project Code: _____
 Site Name: _____
 KDHE UIC Class V Form Completed: ☐ Yes ☐ No
 County/Local Permit Required? ☐ Yes ☐ No
 Permit Obtained? ☐ Yes ☒ No Permit ID: _____
 Oil/Gas Lease Name & Well #: _____

CONSTRUCTION

Casing: Height above land surface: 24 in.
 Is casing height less than 12 inches? ☐ Yes ☒ No
 Blank Casing type: ThermalPlastic
 1st interval: 0 ft. to 340 ft.; Diameter 5 in.
 Casing Joint: : Glued Weight: _____ lbs/ft
 Wall thickness or gauge no.: SDR 21
 2nd interval: _____ ft. to _____ ft.; Diameter _____ in.
 Casing Joint: : _____ Weight: _____ lbs/ft
 Wall thickness or gauge no.: _____
 3rd interval: _____ ft. to _____ ft.; Diameter _____ in.
 Casing Joint: : _____ Weight: _____ lbs/ft
 Wall thickness or gauge no.: _____

Screen / Perforation material: PVC

Specify if other: _____

Screen / Perforation openings: Mill slot

1st interval 340 ft. to 400 ft. Slot Size _____

2nd interval _____ ft. to _____ ft. Slot Size _____

3rd interval _____ ft. to _____ ft. Slot Size _____

WELL WATER USE

Domestic Lawn/Garden

Additional info if required:

of Boreholes

of Dewatering Wells

COMPLETION

Depth of completed well: 400 ft.

Depth(s) groundwater encountered: ☐ Dry Well

(1) 284 ft.; (2) _____ ft.; (3) _____ ft.;

Static water level in well: 284 ft.

Date measured: 03/26/2026

Measured from: ☐ Top of Casing or ☒ Ground SurfaceMeasured: ☐ Above or ☒ Below Land Surface

Estimated yield: 90 gpm

Pump Test Date: Water level was:

_____ ft. after _____ hours pumping _____ gpm

_____ ft. after _____ hours pumping _____ gpm

Pump Information:Pump Installed? ☒ Yes ☐ No Date: 03/27/2026

Pump Type: AC Submer: Horsepower: 5 Volts: 230

Drop Pipe Diameter: 1.2 in. Drop Pipe Length: 340 ft.

Water well disinfected? ☒ Yes ☐ No

Date disinfected (mm/dd/yy): 03/26/2026

CONSTRUCTION**Borehole interval:**

from 0 to 400 ft.

from _____ to _____ ft.

from _____ to _____ ft..

Borehole diameter:

9.75 in.

_____ in.

_____ in.

Grout:

1st Interval: 4 ft. to 25 ft. Grout material: Neat Cement

2nd Interval: 25 ft. to 180 ft. Grout material: Bentonite

3rd Interval: _____ ft. to _____ ft. Grout material: _____

Gravel pack:

Not Used

1st Interval: 180 ft. to 400 ft. Gravel Size: _____ ☐2nd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐3rd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐**DESIGNATED PERSON** Phillip Howard**WELL COMPLETION DATE** 03/25/2026**CONTRACTOR BUSINESS NAME**

Phil-Mar, Inc. d.b.a. Howard Drilling Company

WATER WELL RECORD (WWC-5)

Constructed

KOLAR DOC ID 1977032 WELL ID _____

LOCATION OF WATER WELL

County	Grant	Section	31	Township	28	Range	37	E W Fraction	NW ¼	NW ¼	NE ¼
Latitude	37.575086	Longitude	-101.4074			Datum	NAD83		Elevation	3080	
Well Owner				Well Owner Business			SKYLAND GRAIN				

NEAREST SOURCE OF POTENTIAL CONTAMINATION or ☒ No potential source of contamination within 100 ft.

Source:	Source:
Distance from well (ft):	Distance from well (ft):
Direction from well:	Direction from well:
Source description:	Source description:
Required information for local entity? ☐ Yes ☐ No	Required information for local entity? ☐ Yes ☐ No

LITHOLOGIC LOG**AQUIFER, if known**

FROM	TO	LITHOLOGY
3	90	clay
90	115	clay,sandy
115	155	clay
155	185	clay,sandy
185	250	sand,fine
250	270	sand,coarse
270	335	gravel,coarse
335	365	sand,fine
365	375	gravel,coarse
375	380	sand,fine
380	390	clay
390	400	clay,tannish

COMMENTS

This water well was constructed ☐ reconstructed pursuant to the stated water well contractor's license and was completed on 03/25/2026 .

I certify that this record is true to the best of my knowledge and belief. This water well record was completed on 09/10/2026 under the business name of Phil-Mar, Inc. d.b.a. Howard Drilling Con, KS Water Well Contractor's License No. 430 under the authority of the designated person as defined in K.A.R. 28-30-2(j) and signed and certified by the electronic signature of the designated person at its submittal: Phillip Howard . Send one copy to the water well owner and the contractor should retain one copy.