

WATER WELL RECORD (WWC5.2)

Constructed

KOLAR DOC ID 1982841

WELL ID

LOCATION OF WATER WELL

County	McPherson	Section	9	Township	19	Range	1 ☐ E ☒ W	Fraction	NE ¼ NW ¼ SW ¼
Latitude	38.412866	Longitude	-97.442604	Datum	NAD83	Elevation	1572		

WATER WELL LOCATION☐ at owner's address

~1/2mi N & 900ft E of 26th Ave & Mohawk Rd (1.75mi NNW of Canton, KS)

WATER WELL OWNER

Name	TJ Dearing
Business	
Address	1205 Turkey Creek Dr McPherson KS 67460

PERMIT & ID NUMBERS (AS REQUIRED)

DWR Application No.: _____

KDHE / EPA Project Code: _____

Site Name: _____

KDHE UIC Class V Form Completed: ☐ Yes ☐ No

County/Local Permit Required? ☐ Yes ☐ No

Permit Obtained? ☒ Yes ☐ No Permit ID: SA-26-0133-W

Oil/Gas Lease Name & Well #: _____

CONSTRUCTION

Casing: Height above land surface: 12 in.

Is casing height less than 12 inches? ☐ Yes ☒ No

Blank Casing type: ThermalPlastic

1st interval: 0 ft. to 22 ft.; Diameter 5 in.

Casing Joint: : Glued Weight: _____ lbs/ft

Wall thickness or gauge no.: .214

2nd interval: _____ ft. to _____ ft.; Diameter _____ in.

Casing Joint: : _____ Weight: _____ lbs/ft

Wall thickness or gauge no.: _____

3rd interval: _____ ft. to _____ ft.; Diameter _____ in.

Casing Joint: : _____ Weight: _____ lbs/ft

Wall thickness or gauge no.: _____

Screen / Perforation material: PVC

Specify if other: _____

Screen / Perforation openings: Mill slot

1st interval 22 ft. to 82 ft. Slot Size .025 inches

2nd interval _____ ft. to _____ ft. Slot Size _____

3rd interval _____ ft. to _____ ft. Slot Size _____

WELL WATER USE

Domestic Household

Additional info if required:

of Boreholes

of Dewatering Wells

COMPLETION

Depth of completed well: 82 ft.

Depth(s) groundwater encountered: ☐ Dry Well

(1) 32 ft.; (2) _____ ft.; (3) _____ ft.;

Static water level in well: 32 ft.

Date measured: 09/14/2026

Measured from: ☐ Top of Casing or ☒ Ground SurfaceMeasured: ☐ Above or ☒ Below Land Surface

Estimated yield: 30 gpm

Pump Test Date: Water level was:

_____ ft. after _____ hours pumping _____ gpm

_____ ft. after _____ hours pumping _____ gpm

Pump Information:Pump Installed? ☐ Yes ☒ No Date:

Pump Type: _____ Horsepower: _____ Volts:

Drop Pipe Diameter: _____ in. Drop Pipe Length: _____ ft.

Water well disinfected? ☒ Yes ☐ No

Date disinfected (mm/dd/yy): 09/14/2026

CONSTRUCTION**Borehole interval:**

from 0 to 82 ft.

from _____ to _____ ft.

from _____ to _____ ft..

Borehole diameter:

9 in.

_____ in.

_____ in.

Grout:

1st Interval: 0 ft. to 20 ft. Grout material: Bentonite

2nd Interval: _____ ft. to _____ ft. Grout material: _____

3rd Interval: _____ ft. to _____ ft. Grout material: _____

Gravel pack:

Not Used

1st Interval: 20 ft. to 82 ft. Gravel Size: _____ ☐2nd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐3rd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐**DESIGNATED PERSON** Austin Hart**WELL COMPLETION DATE** 09/14/2026**CONTRACTOR BUSINESS NAME** Peterson Drilling, LLC - #1099

LOCATION OF WATER WELL

County	McPherson	Section	9	Township	19	Range	1	☐ E ☒ W	Fraction	NE ¼	NW ¼	SW ¼
Latitude	38.412866	Longitude	-97.442604		Datum		NAD83		Elevation	1572		
Well Owner	TJ	Dearing		Well Owner Business								

NEAREST SOURCE OF POTENTIAL CONTAMINATION or ☒ No potential source of contamination within 100 ft.

Source:	Source:
Distance from well (ft): Direction from well:	Distance from well (ft): Direction from well:
Source description:	Source description:
Required information for local entity? ☐ Yes ☐ No	Required information for local entity? ☐ Yes ☐ No

LITHOLOGIC LOG

AQUIFER, if known[illegible]

COMMENTS

Journal of Management Education, 31(1), 1-14. doi:10.1177/0095647206289211
 Journal of Management Education, 31(1), 1-14. doi:10.1177/0095647206289211
 Journal of Management Education, 31(1), 1-14. doi:10.1177/0095647206289211

This water well was ☐ constructed ☐ reconstructed pursuant to the stated water well contractor's license and was completed on 09/14/2026.
I certify that this record is true to the best of my knowledge and belief. This water well record was completed on 09/15/2026 under the business name of Peterson Drilling, LLC - #1099, KS Water Well Contractor's License No. 1099 under the authority of the designated person as defined in K.A.R. 28-30-2(j) and signed and certified by the electronic signature of the designated person at its submittal: Austin Hart. Send one copy to the water well owner and the contractor should retain one copy.