

WATER WELL RECORD (WWC5.2)

Constructed

KOLAR DOC ID 1985344

WELL ID _____

LOCATION OF WATER WELL

County	Norton	Section	18	Township	4	Range	25 ☐ E ☒ W	Fraction	SE ¼ SE ¼ NE ¼
Latitude	39.704834	Longitude	-100.171173	Datum	WGS84	Elevation	2570		

WATER WELL LOCATION☐ at owner's address

2.5 miles south of clayton

WATER WELL OWNER

Name	Darla Ellis
Business	
Address	311 West Ave Norton KS 67654

PERMIT & ID NUMBERS (AS REQUIRED)

DWR Application No.: _____
 KDHE / EPA Project Code: _____
 Site Name: _____
 KDHE UIC Class V Form Completed: ☐ Yes ☐ No
 County/Local Permit Required? ☐ Yes ☐ No
 Permit Obtained? ☐ Yes ☐ No Permit ID: _____
 Oil/Gas Lease Name & Well #: _____

CONSTRUCTION

Casing: Height above land surface: 18 in.
 Is casing height less than 12 inches? ☐ Yes ☒ No
 Blank Casing type: ThermalPlastic
 1st interval: 0 ft. to 190 ft.; Diameter 4 in.
 Casing Joint: : Glued Weight: 200 lbs/ft
 Wall thickness or gauge no.: _____
 2nd interval: _____ ft. to _____ ft.; Diameter _____ in.
 Casing Joint: : _____ Weight: _____ lbs/ft
 Wall thickness or gauge no.: _____
 3rd interval: _____ ft. to _____ ft.; Diameter _____ in.
 Casing Joint: : _____ Weight: _____ lbs/ft
 Wall thickness or gauge no.: _____

Screen / Perforation material: PVC

Specify if other: _____

Screen / Perforation openings: Mill slot

1st interval 190 ft. to 210 ft. Slot Size .016 millim

2nd interval _____ ft. to _____ ft. Slot Size _____

3rd interval _____ ft. to _____ ft. Slot Size _____

WELL WATER USE

Domestic Livestock/Pasture

Additional info if required:

of Boreholes

of Dewatering Wells

COMPLETION

Depth of completed well: 210 ft.

Depth(s) groundwater encountered: ☐ Dry Well

(1) _____ ft.; (2) _____ ft.; (3) _____ ft.;

Static water level in well: 140 ft.

Date measured: 09/23/2026

Measured from: ☒ Top of Casing or ☐ Ground SurfaceMeasured: ☐ Above or ☒ Below Land Surface

Estimated yield: 12 gpm

Pump Test Date: Water level was:

_____ ft. after _____ hours pumping _____ gpm

_____ ft. after _____ hours pumping _____ gpm

Pump Information:Pump Installed? ☐ Yes ☒ No Date:

Pump Type: _____ Horsepower: _____ Volts: _____

Drop Pipe Diameter: _____ in. Drop Pipe Length: _____ ft.

Water well disinfected? ☒ Yes ☐ No

Date disinfected (mm/dd/yy): 09/23/2026

CONSTRUCTION**Borehole interval:**

from 0 to 210 ft.

from _____ to _____ ft.

from _____ to _____ ft..

Borehole diameter:

9.8 in.

_____ in.

_____ in.

Grout:

1st Interval: 0 ft. to 25 ft. Grout material: Bentonite

2nd Interval: _____ ft. to _____ ft. Grout material: _____

3rd Interval: _____ ft. to _____ ft. Grout material: _____

Gravel pack:

Not Used

1st Interval: 25 ft. to 210 ft. Gravel Size: _____ ☐2nd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐3rd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐**DESIGNATED PERSON** Richard Wilcox**WELL COMPLETION DATE** 09/22/2026**CONTRACTOR BUSINESS NAME** Wilcox Well Drilling LLC

WATER WELL RECORD (WWC-5)

Constructed

KOLAR DOC ID 1985344 WELL ID _____

LOCATION OF WATER WELL

County	Norton	Section	18	Township	4	Range	25	E W Fraction	SE	¼	SE	¼	NE	¼
Latitude	39.704834	Longitude	-100.171173			Datum	WGS84	Elevation		2570				
Well Owner	Darla	Ellis			Well Owner Business									

NEAREST SOURCE OF POTENTIAL CONTAMINATION or ☒ No potential source of contamination within 100 ft.

Source:	Source:
Distance from well (ft):	Distance from well (ft):
Direction from well:	Direction from well:
Source description:	Source description:
Required information for local entity? ☐ Yes ☐ No	Required information for local entity? ☐ Yes ☐ No

LITHOLOGIC LOG**AQUIFER, if known**

FROM	TO	LITHOLOGY
0	5	topsoil
5	48	sand, fine
48	60	clay-fat
60	62	limestone, highly weathered
62	101	sandstone, moderately weathered
101	103	limestone, moderately weathered
103	137	clay-fat
137	141	limestone, moderately weathered
141	152	clay-lean
152	167	sand & gravel, fine to medium
167	172	clay-lean
172	203	sand & gravel, fine to coarse
203	205	clay
205	208	gravel, coarse
208	210	shale, slightly weathered

COMMENTS

This water well was constructed ☐ reconstructed pursuant to the stated water well contractor's license and was completed on 09/22/2026.

I certify that this record is true to the best of my knowledge and belief. This water well record was completed on 09/24/2026 under the business name of Wilcox Well Drilling LLC, KS Water Well Contractor's License No. 701 under the authority of the designated person as defined in K.A.R. 28-30-2(j) and signed and certified by the electronic signature of the designated person at its submittal: Richard Wilcox. Send one copy to the water well owner and the contractor should retain one copy.