


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CITIENS SERVICE OIL CO.
Farm - F. H. Adsit No. 20

SEC. 36 T. 25 R. 1E
NE SE NW
330' W & 990' N of Center'

Total Depth. 2461'
Comm. 2-10-49 Comp. 3-19-49
Shot or Treated. Shot 1/40 qts. 2436-2461'
Contractor. B. & R. Drig. Inc.
Issued. 6-4-49

County. Butler
KANSAS



Elevation. 1396' Ind

CASING:
8-5/8" 78'7" Cem. W/ 60 Sz.
5-1/2" 2430' Cem. W/150 Sz.

Production. 150 BO, no wtr, 24 hrs.
H.P.O. (after shot)

Figures Indicate Bottom of Formations.

top soil	4
lime-	47
shale lgt	53
lime	76
shale lgt	81
lime & shale	265
lime	589
shale & lime	750
shale & shells	1071
shale & lime	1858
lime	1918
shale & lime	2433
dolomite	2461
Total Depth	

Steel Line Measure:

484 = 484
976 = 976
1602 = 1604
1940 = 1940
2400 = 2400
R.T.C. 2433'

Top:

Lansing	1717
Base Lansing	1843
Kansas City	1948
Base Kansas City	2148
Arbuckle	2429

1749-53' very small show oil
1820-23' very small show oil
2004-21' small show oil
2025-40' small show oil
2058-72' small show oil
2429-41' show oil
-46 good show oil
-48 show of oil
-50 small show oil
-59 good show oil
-61 fair show oil

2429
1306

1123

Best pay 2441-46, 2450-61'
First free oil 2433'
Fillup 330' oil, no wtr, 14 hrs.
Shot 1/40 qts. 2436-2461'
Fillup after show 2200' oil,
no wtr, while cleaning out.