


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, , Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - W.H. Adsit No. 22

SEC. 36 T. 25 R. 4E
CE/2 SW NW
660' N, 990' E of $\frac{1}{4}$ corner

Total Depth. 2455 SLM
Comm. 8-7-49 Comp. 8-24-49
Shot or Treated. Shot
Contractor. B & R Drlg., Drilling by C. L. Roberts
Issued. 10-8-49

County. Butler
KANSAS



CASING:
8 5/8" 71' cem w/85 sx.
5 1/2" 2425' cem w/150 sx.

Elevation. 1386 Ind

Production. 30 bbls oil, 65 bbls water, 24 hrs.

Figures Indicate Bottom of Formations.

top soil	4
lime	27
shale	38
lime	290
lime, shale	1790
lime	1861
lime, shale	2425
dolomite	2455
Total depth SLM	

Tops:

Lansing lime	1725
Base Lansing lime	1844
Kansas City lime	1995
Base K.C. lime	2165
Erosional zone	2420
Base Erosional zone	2425
Arbuckle dolomite	2425

Straight hole survey:
500' OK
1000' OK
1300' OK
1900' OK

Steel line measure:

500 = 500
1132 = 1135
1415 = 1416
1977 = 1978
2405 = 2405
2451 = 2455

R.t.D. 2426

1758-65, SSO

2000-06, SSO

2010-13, SO

2021-40, SO

2420-25, NSO

2425-27, SSO

2427-35, SO

2435-39, SSO

2439-41, FSO

2441-49, GSO

2449-51, FSO

1st free oil 2439-42, (VSSFO)

Best pay 2441-49.

Correction 2451-2455' SLM

Every sample carried green shale, sand and pyrite. Bailed 1/3 bbl. oil, 0 water at 2449'.

Fill UP: 250' oil, 0 water, 36 hrs. at 2455'.

Shot w/40 qts. OWE from 2434-2450. 1700' fluid (1500' oil, 200' wtr, bailed bottom wtr.)

in hole after C.O. on bottom.

I. P. 30 bbls. oil, 65 bbls. water, 24 hrs,

N.P.O. (mach.) (after shot).