


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

10-15-26W
SEQ. 10 T. 15 R. 26W
C SE SW

Company- TIME PET CO. & ASSOC.
Farm- J. Bollinger No. 1

Total Depth. 4360' (4361)
Comm. 5-4-64 Comp. 5-17-64
Shot or Treated.
Contractor. Empire Drilling Company
Issued. 8-8-64

County Gove
KANSAS



Elevation. 2405' KB

Production. Dry

Figures Indicate Bottom of Formations.

surface-sand-clay-shale	127
shale & sand	1836
Anhydrite	1872
shale	1990
shale & shells	2207
salt	2323
shale & lime	2358
shale-shells	2510
lime & shale	3710
lime & chert	3748
lime & shale	3910
lime	3955
lime-chert	3986
lime & shale-lime	4210
lime-chert	4240
lime-shale	4285
chert & lime	4299
Mississippi	4310
Mississippi Dolomite	4320
Mississippi	4360 RTD
Total Depth	

TOPS: SCHLUMBERGER ELECTRIC LOG

Waubesa	3256
Topeka	3440
Queen Hill	3522
Heebner	3652
Toronto	3675
Lansing	3690
Muncie Creek	3846
Base Kansas City	3988
Pawnee	4096
Ft. Scott	4134
Cherokee Group	4190
Basal Pennsylvanian Conglomerate	4275
Mississippi	4298