

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

27-15-26W

Company. EMPIRE DRILLING

Farm. Doerr

No. 2

SEC. 27 T. 15 R. 26 W

C NE SW

Total Depth. 4483'


Comm. 5-18-64

Comp. 6-4-64

Shot or Treated.

Contractor. Empire Drlg.

Issued. 8-15-64

County Gove
KANSAS

CASING:

Elevation. 2504' KB

10 3/4" 91' cem w/ 60 sx

5 1/2" 4482' cem w/ 50 sx

Production. 109 BOPD 5% WTR

Figures Indicate Bottom of Formations.

surface shale clay	75
shale	105
shale & shells	800
sand-shale & shells	1710
red bed	1922
anhydrite	1958'
shale & shells	1965
shale	2297
salt	2404
shale & shells	2600
lime & shale	3840
lime w/ chert	3865
lime & shale	4050
cherty lime	4085
lime & shale	4275
lime-sand	4305
lime & shale	4390
Mississippi	4400
Dolomite	4405
Mississippi	4483 RTD
Total Depth	

TOPS: LOG	
ANHYDRITE	1922
Aaubansee	3338
Shawnee (Topeka)	3524
Queen Hill	3606
Heebner	3738
Toronto	3758
Lansing	3780
Muncie Creek	3928
Base Kansas City	4076
Pawnee	4176
Fort Scott	4218
Cherokee Group	4272
Conglomerate	4352
Mississippi lime	4369
Solid Mississippi	
Dolomite	4393
Osage	4454