


27-15-26W

County Gove KANSAS

Total Depth. 4382'
Comm. 1-8-64 Comp. 1-26-64
Shot or Treated.
Contractor. Empire Drlg.
Issued. 5-23-64



CASING:

Elevation. 2509' KB

8 5/8" 108' cem w/ 50 sx
5 1/2" 4374' cem w/ 200sx

Production. 121 BOPD

Figures Indicate Bottom of Formations.

surface shale	133
shale & pyrite	890
shale-shells- Pyrite	1171
shale & shell	1350
Gypsum & shale	1510
Red bed & sand	1932
anhydrite	1970
shale	2060
shale & lime	2307
salt	2415
shale	2530
lime & shale	2700
lime	2865
lime & shale	3113
lime	3283
shale & lime	3375
lime	3576
chalky lime & shale	3640
lime	3755
cherty lime	3830
lime-chert	3865
cherty lime & shale	3900
lime w/chert	3960
lime w/ chert & shale	3990
lime	4025
lime & shale	4050
chert-lime-shale	4095
lime & shale	4153
lime	4200
lime & shale	4280
lime	4305
lime w/shale	4335
lime	4345
lime-shale	4350
lime	4354
Mississippi	4382
Total Depth	RTD

Paw nee	4179
Fort Scott	4220
Cherokee	4271
Cherokee limestone	4280
reworked Mississippian	4350
Solid Mississippian	4371

TOPS: LOG	
Anhydrite	1930
Wabaunsee	3345
Topeka	3530
Queen Hill	3610
Heebner	3743
Toronto	3764
Lansing	3783
Muncie Creek	3929
Base Kansas City	4079