

KANSAS

PL

IMPORTANT
Kans. Geo. Survey request
samples on this well.

WELL COMPLETION REPORT AND
DRILLER'S LOG

S. 27 T. 15S R. 26 E W

Loc. 150's NE SE

County GOVE *State Geological Survey
WICHITA, BRANCH*
640 Acres
N

API No. 15 — 063 — 20,428
County Number

Operator
Kansas Oil Corporation

Address
250 N. Rock Road, Suite 300, Wichita, KS 67206


Well No. #1 Lease Name Wells

Footage Location
feet from (N) (S) line feet from (E) (W) line

Principal Contractor D N B Drilling, Inc. Geologist Charles V. Shank

Spud Date 8/4/79 Date Completed 8/11/79 Total Depth 4510 P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser



Elev.: Gr. 2493
DF 2496 KB 2498

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20# n	290'	common	200	2% gel, 3%cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION D & A

Date of first production	Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be trans-
mitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation
Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note
Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Kansas Oil Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

#1

Lease Name

Wells

Dry Hole

S 27 T 15 R 26 E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Anhydrite	1916			
Heebner	3745			
Lansing	3786			
Pawnee	4230			
Ft. Scott	4294			
Cherokee Shale	4321			
Conglomerate	4392			
Miss. Lime	4412			
Miss Dolomite	4444			
DST #1, 30-30-30-30, Rec. 65' GCM w/ few specks oil	3970	4030		
IFP - 86-64				
FFP - 107-86				
ISIP - 899				
FSIP - 857				
BHT - 126°				
DST #2, 30=30-30-30, REc. 90'm w/ spks oil	4285	4321		
IFP - 102-102				
FFP - 102-102				
FSIP - 725				
BHT - 111°				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Michael R. Bryan
Signature

Michael R. Bryan

Title

3/24/81

Date

PI

27-15-26W

DRILLER'S LOG

KANSAS OIL CORPORATION
No. 1 Wells
150'S NE SE
Sec. 27-15S-26W
Gove Co., Ks.

Commenced: 8-4-79
Completed: 8-11-79

Surface Casing: 283' of 8-5/8"
cemented w/200 sx common, 2% gel,
3% cc

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 290
Shale	290 - 730
Shale & Sand	730 - 1349
Blaine	1349 - 1361
Shale, Sand & Red Bed	1361 - 1760
Shale	1760 - 2270
Lime & Shale	2270 - 3770
Lime	3770 - 4030
Lime & Shale	4030 - 4085
Lime	4085 - 4420
Chert	4420 - 4472
Lime	4472 - 4510 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess
Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 16th day of August, 1979.

Dorothy L. Schmidt
Dorothy L. Schmidt, Notary Public

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1983